

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

9-28-17E

COMPANY ~~GAMBLE-WRIGHT-CRUMLEY~~

SEC. 9 T. 28 R. 17E

FARM Ed Parr

NO. 1

LOC. E/2 SW

TOTAL DEPTH 1079

COUNTY Wilson

COMM.


COMP. 9-1-18

SHOT OR TREATED

CONTRACTOR

ISSUED

KANSAS



CASING

20	10'
15	8 1/4" 396'
12	6 1/4" 732'
13	5 1/4" 967'

ELEVATION

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

soil	2	shale wht	1057
lime, shells	11	sandy shale blue	1077
shale	100	sand wht	1079
water at 110'		Total Depth	
lime	110		
shale	115		
lime	120		
sand	230		
shale	235		
lime	310		
shale	315		
sand	325		
sandy shale	350		
lime	373		
shale drk	388		
lime	396		
hole reduced 396 SLM			
lime	421		
shale	525		
lime	535		
lime, shells	550		
shale	622		
lime	625		
shale	630		
lime	655		
shale drk	665		
lime	667		
shale	694		
lime	711		
20' SLM at 699'			
slate	717		
lime	727		
slate	732		
lime	734		
sand	739		
shale	868		
sand	873		
little gas SLM at 873'			
sand	890		

no gas	
sand little gas	897
sand	912
sand water 1/2 BW	930
shale	967
sandy shale	1031
sand wht	1034
225,000 Gas	
sand wht no gas	1036
sand	1038
280,000 Gas	
sand no gas	1039
sand no gas	1040
sand	1042
225,000 Gas	
sand no gas	1047