

State KANSAS County OSBORNE

Company Messman-Rinehart Corp. Well No. 1


Farm MEYERS "A"

Contractor:
~~xxxx~~ Dreiling Oil, Inc.

Block No. _____ Sec. 7 Twp. 10S Range 14W

Co-Ord. _____ Elev. 1937' Gr.

App. 50' N of C SW SE 1942' KB



D & A

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
10-25-78		MIRT - Rig up - Spud 3:50 p. Run 8 5/8" set @ 293', 180 sx. cem., 2% Gel, 3% calcium chloride. Plug down 11:00 p. Cement circulated
10-26-78		WOC
10-27-78		Dr1. 1752
10-28-78		Dr1. 2515

717007

Date	Depth	
10-29-78		Anyh. 1189 + (753)
		Tarkio LM 2741 - (799)
		DST - Tarkio 2654-2745:
		Open 15 min., SI 20 min.,
		Open 30 min., SI 30 min. Weak
		blow, died 14 min. after 2nd
		open. Rec. 40' rotary mud.
		IBHP 876, IF 63, FF 74,
		FBHP 854, Temp. 88 ⁰
10-30-78		Heebner 3146 (-1204)
		Lansing 3198 (-1256)
		DST - 3206-3240: Open 30
		min., SI 20 min., open 30 min
		SI 30 min., Weak blow, Rec.
		60' Mud. No Show.
		IBHP 654, IFP 53, FBHP 886,
		FFP 63, Temp. 98 ⁰
10-31-78		Dr1. @ 3390'
11-1-78		Congl. 3599 (-1657)
		3599-3648 - Shly w/little
		chert & very little sand.
	3648	top of Cherty Cong. No shows
		Sniffer recorded no shows
	3655	Dr1g. Top Viola 3702 (-1760)

R.T.D. 3710' - P & A

No electric log run.