

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

18-32-4E

COMPANY LONITA OIL CORPORATION, INC.

SEC. 18 T. 32 R. 4E

FARM Lawrence

NO. 1

LOC. NE NE NW

TOTAL DEPTH 3397

COMM. 2-25-67


COMP. 3-8-67

COUNTY Cowley

SHOT OR TREATED

CONTRACTOR Watson Drlg.

ISSUED 4-22-67



CASING

20	10	
15	8	5/8" @ 216' w/ 150 sx
12	6	
13	5	

ELEVATION 1129' KB

PRODUCTION DRY/ARB

FIGURES INDICATE BOTTOM OF FORMATIONS

0	25	surface clay	
25	45	Gravel	
45	50	lime and shale	TOPS: SCOUT
50	190	lime and shale	Howard 1136
190	216	lime	Topeka 1268
216	235	lime	Iatan 1933
235	360	lime and shale	Stalnaker 1950
360	590	lime and shale	Layton 2376
590	990	shale - lime	Kansas City 2475
990	1185	shale and lime	Cleveland 2645
1185	1425	lime and shale	Cherokee 2817
1425	1508	lime - shale	Cattlemen 2827
1508	1520	sand	Bartlesville 2977
1520	1625	shale - sand - shale	Mississippi 3010
1625	1800	shale and lime	Simpson 3344
1800	1933	shale	Arbuckle 3351
1933	1939	lime (Iatan)	
1939	1960	shale and sand	
1990	2056	sand - shale	
2056	2163	shale	
2163	2175	sand	
2175	2230	shale	
2230	2341	shale	
2341	2374	shale	
2374	2412	sand and shale	
2412	2482	sand - shale	
2482	2557	lime	
2557	2640	lime	
2640	2660	shale and sand	
2660	2699	sand	
2699	2775	lime	
2775	2816	lime - shale	
2816	2852 s	sand - shale	
2852	2900	shale	
2900	3010	shale	
3010	3015	sand and shale	
3015	3022	lime	
3022	3046	lime	
3046	3100	lime	
3100	3148	lime	
3148	3190	lime	
3190	3260	lime	
3260	3302	lime and shale	
3302	3344	shale	
3344	3347	sand (Simpson)	
3347	3351	sand	
3351	3353	lime	Plugged hole - mud to 225' - 1/2
3353	3360	lime	sack hulls. Plug 20 sacks cement
3360	3397	lime	mud to 35' - 1/2 sack hulls.
3397	3397	T.D.	Plug - 8 sacks cement - 2 sacks
			cement in rat hole.

We certify that the above log is true and correct to the best of our knowledge and belief.

WATSON DRILLING CO., INC.

By

*[Handwritten Signature]*