

State Kansas County Barton

Company Messman - Linchert Corp. Well No. 1


Farm Kinderdeck

Survey

Block No. Sec. 6 Twp. 19<sup>v</sup> Range 12<sup>w</sup>

Co-Ord. NE SE SE Elev. 1819 KIB  
1808 G.V.

Center - white & Ellis Oily.



50% Royalty Messman  
50% P. B. Linchert

3450' Arbuckle test

NOTE: Show Sketch of Lease and Well Location in Above Space


Ft. from N. Line ~~1900~~ <sup>990</sup> Ft. from S. Line  
Ft. from W. Line ~~1900~~ <sup>900</sup> Ft. from E. Line

Date	Depth	
6-18-81		M. J. R. J.
6-19		8 <sup>5</sup> / <sub>8</sub> ' @ 258' w/175 sq. corn, 370 gal., 2% c.c. P. D. @ 12:00 noon 6/19/81
6-20	968	Oily
6-21	1930	Oily
6-22	2548	Oily.
6-23	2731	Oily (down w/ trouble w/BQ hook)

Date	Depth	717315
6-24	2978	Oelg.
6-25	2994	Hebner (-1175)
	3097	Budm. (-1278)
	3109	Lanning (-1290)
		O.S.J. #1 - 3112-67' - op. 30" si 30" - op. 30" si 30" wh. bl. & Rec. 3' mud isip - 56 <sup>#</sup> - fp. 33-33 <sup>#</sup> fsip - 45 <sup>#</sup> (Going back in hole)
6-26	3270	Oelg. Depth (an bottom w/ 815 <sup>#</sup> 2
		O.S.J. #2 - 3228-70' - op. 30" at 30" - op. 30" si 30" wh. bl. dild in 25", Rec. 5' mud. ikhp 78 - fp. 56-56 I S P - 67
6-27		O.S.J. #3 - 3267-3330 - op. 30"
		bl. 30", op. 30" si 30" wh. bl dild in 25", Rec 5' mud. I S P 78 - fp. 56-56 fsip - 67
6-28		O.S.J. #4 - 3355-3405' - op. 30"
		si 30", op. 60", si 45", wh. bl Rec. 5' sli cut cut, mud isip 326 - fp. 45-45 fsip - 304
6-28	3420'	R.S.O. R + a - 6-28-81

State Kansas County Barton  
 Company Messner-Leubach Co. Well No. 1  
 Farm Kinderhook  
 Survey \_\_\_\_\_  
 Block No. \_\_\_\_\_ Sec. 6 Twp. 19<sup>N</sup> Range 12<sup>W</sup>

Co-Ord. W 1/4 Sec 36 Elev. 1819 17B  
1808 Gv.  
 Cont. - white - Ellis Shaly.



50% - Roger L. Messner  
 50% - P. B. Leubach

3450' Arbuckle Test

NOTE: Show Sketch of Lease and Well Location in Above Space

990

Ft. from N. Line 1000 Ft. from S. Line \_\_\_\_\_  
 990  
 Ft. from W. Line 1000 Ft. from E. Line \_\_\_\_\_

Date	Depth	
		<u>Sample Taps</u>
	<u>1584</u>	<u>Herrington Kinder (+235)</u>
	<u>1634</u>	<u>Wenfield (+185)</u>
	<u>1702</u>	<u>Towanda (+117)</u>
	<u>1733</u>	<u>Ft. Riley (+86)</u>
	<u>1831</u>	<u>Base Florence (-12)</u>
	<u>2061</u>	<u>Kewa <sup>(Flint)</sup> (-242)</u>
	<u>2453</u>	<u>Jarkio (-634)</u>
	<u>2653</u>	<u>Tapeha (-834)</u>

