


State Kansas County Barton
Company Messmer-Linckait Corp. Well No. 3
Farm West.

Survey

Block No. . Sec. 24 Twp. 19 Range 14 ^W

Co-Ord. Elev. 1871 ^{K/B}
1868 ^{DF}



Ch. Surf Conts. Woodman & Sonette
50% - Condor Energy
* 25% - Ray, Y. Messmer
25% - C. B. Linckait

* Subj. to 44% of this int. to
diminish as ORD.
1/2 x 7/8 - less or
1/2 x 7/8 - J. Geo. Klein

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 1320 Ft. from S. Line

1320 Ft. from W. Line Ft. from E. Line

Date	Depth	
<u>3-11-83</u>		<u>M. J. R. J.</u> <u>Land - 2:00 P.M.</u> <u>8 5/8" @ 790' w/ 290' of 60/40</u> <u>perm. 3% @ 290' w/</u> <u>100' of common cen</u> <u>3 7/8" C.C. 290' w/</u> <u>P.W. @ 3:45 a.m. - 3/12/83</u>
<u>3-14</u>	<u>2828</u>	<u>Dily.</u>
	<u>978</u>	<u>Anhydrite (#1093)</u>
<u>3/15</u>	<u>(Garanty)</u>	<u>J. #1 - 3094 - 3160 - 4 3/4" 30"</u> <u>ri 30" op 75" ri 60"</u>

Date	Depth	
		717336
		Rec. 40' oil-specked mud.
		BHP-600-760 [#]
		I.D. - 53.53 [#] , Temp. 100°
		Bring back in hole to ducer ahead
	3187	Brown Ln (-1316)
	3200	Lansing (-1329) 11' low
	3210	φ
3-16	10.1.1.1 [#]	2-3340-92-op. 30" 1130"
		op. 60", si 60", good blow
		Rec. 30' 0' gas in pipe
		30' 1970 mud
		2170 wtr.
		1270 oil
		4890 gas
	30'	2970 mud
		3170 wtr.
		1570 oil
	60'	2570 gas
		7070 mud
		1170 wtr.
		870 oil
		1170 gas
		S.P. - 888-878 [#] , Z.P. 75.85 [#]
		(Thinned up 5' - 6' low)
3-17	3483	Arbuckle (-1612)
	3486	(flat w/ #2 on Arbuckle stop dip. 4' corr.)
	10.1.1.1 [#]	3-3432-90-op. 30", cl 30"
(7' in arb. - very tight)		op. 30", si 60", wh. bl.
		Rec. 10' oil-sphd mud
		BHP 214-429 [#]
		Temp 106.° F 53.5

State

Kansas

County

Barton

Company

Messmer Linhart Co.

Well No.

3

Farm

West

Survey

Block No.

Sec.

24

Twp.

19

Range


14

Co-Ord.

Elev.

Ch. 1/4

Page 2



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

1320

Ft. from S. Line

1320

Ft. from W. Line

Ft. from E. Line

Date

Depth

3-18

O. L. J. #4 - 3432-98 -

op. 30", ri 30", op. 30"
ri 60", wh. bl.gas 30", Rec. 30' gas
30' oil-saturated mud
BHP - 1038 - 1091FP. 53-53th imp 106°

O. L. J. #5 - 3489-3506'

op 30" ri 30" op 90" ri 60"

Date	Depth	717336
		wh. bt. throughout
		Rec. 140' oil. specks mud, etc.
		60' (68% mud, 32% wtr.)
		80' (30% mud, 70% wtr.)
		SDP - 1102 - 1091 th
		Sp 64-96 th temp 111°
3/19	3633	R. J. W.
		Ran Electric Elec. Log
		5 1/2" @ 3540. 4/125 x 4
		60-40 perm. 1% gel
		5% gilsonite
		PD 3:30 P.M. 3/19/83
5/27		M. L. C. J.
		1500' fillup w/wh in
		Airbrake would not
		crack down
6/1	(L-1)	Set Plug @ 3420'
		Ref. 3343-47
		3358-61
		Coring 4/500 ft. d. (152)
		1200 th top - Break to 500 th
		5 1/2 bpm @ 550-500. Vac. inst. on
		Subg. 1 baph. - 2 hrs.
6-2		20 th pr. on csg.
		Fillup overnite - 600'
		(150' oil - 450' wtr.) 4 hrs.
6-3		Subg. 4 baph. - 4 hrs.
		(30% oil) 4 hrs.
6-18		Completed 5 baph.