

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


21-16-25W

Company- PICKRELL DRILLING COMPANY  
Farm- Mollenkamp "A" No. 1

SEC. 21 T. 16 R. 25W  
C SW SW

Total Depth. 4580'  
Comm. 7-23-62 Comp. 8-5-62  
Shot or Treated.  
Contractor.  
Issued. 12-8-62

County NESS  
KANSAS



Elevation. 2581' RB

Production. 97 BOPD, NW

CASING:

8 5/8" 300' cem w/170 sx.  
5 1/2" 4578' cem w/100 sx.

Figures Indicate Bottom of Formations.

(Meas. from top of RB)

soil & yellow clay	58
shale & sand	90
grey shale	260
shale	685
sand	725
shale	810
sand	1065
shale	1150
sand	1200
red bed & shale	1345
Blaine	1370
red bed, shale & shells	1425
sand	1460
shale	1480
sand	1680
red bed & shale	1950
anhydrite	1985
shale & shells	2260
lime & shale	2800
lime	2975
lime & shale	3625
lime, shale & sand	3800
lime	3960
lime & shale	4050
lime	4222
lime & shale	4498
shale	4507
Mississippi-Chert	4519
Mississippi	4580 RTD
Total Depth	

TOPS: LOG

Blaine	1354
Anhydrite	1950
Heebner	3865
Lansing	3904
Fort Scott Lime	4409
Mississippi	4508