


State KANSAS County RICE
 Company N E R Well No. 1
 Farm WAHL 'A'
 Survey SW-NW-NE

Block No. _____ Sec. 3 Twp. 20^S Range 7^W
 Co-Ord. Mitchell Energy Elev. 1720 DG
1793 KB



Interested owners
 R. L. M.
 C. A. R.
 Barbara C. Linchbach, Wash
 Alice Messman
 Geo. George Klein
 Frank. Red Liger, Wyo

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
1973		
11-15		MIRT Spud
		Drill 263' 12 1/4" hole
		run to top 85 1/8" 8rd
		362.32'
		used csg 255.32' sch
		262.32' Cemented
		w/ 155 sh common
		3% calcium chloride
		2% Gel Plug down
		8:30 pm - Allied

717365

Date	Depth	
11-16		Element circulated
11-17	1645	Ø plug
11-18	2554	Ø
11-19	2965	Ø
11-20	3218	Ø
11-21		DST #1 3215-166
		Open 30" ^{S.I. 30} Rec. 20 ^{Open 30} 51 30
		Rec 30' mud, FP 53-53
		ISIP 81 [#] , FBHP 59 [#]
		DST #2 3304-17
		Open 11' 10" - string bl. to Rec.
		1150' gas, 10' M. ISIP 169 [#] IF 42 [#]
		FP 42 [#] FSIP 355 [#] Open 45 min
		S.I. 30" Open 90 min 51 50 min.
		To drill ahead
11-22		DST #3 3317-3332
		open 30 min. S.I. 30" open
		30" S.I. 30" Weak blow
		dead in 30 min. Rec. 15'
		thin mud. IBHP 51 [#] IFP 24 [#]
		FFP 24 [#] FBHP 24 [#] Temp 104
11-22	3380	T.D. D & A.
	3375	Heeb. 2725' (-1002')
		Bin Lm 2871' (-1148')
		Lans. 2905' (-1182')
		Miss 3304' (-1581')
		Kind 3328' (-1605')
		T.D. 3380 3375

sample
tops

No electric log run.