

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

59860

✓

Company - FALCON SEABOARD DRILG.CO.-SOHIO OIL
Farm - Frevele No. 1.

SEC. 22 T. 16 R. 25 W
C SE SE


DISCOVERY WELL

Total Depth. 4564'
Comm. 10-8-43
Shot or Treated.
Contractor.
Issued. 3-11-44

Comp. 11-8-43

County.

Ness
KANSAS



CASING:

8 1/2" 190'
7" 4526' Cem.

Elevation. _____

Production. Pot. 142 B.

Figures Indicate Bottom of Formations.

surface clay	0-63
sand	81
shale & shells	555
lime & shale	675
shale & shells	705
sand	725
shale & shells	825
sand & shale	950
shale & shells	1555
red bed & shells	1910
shale & mica	1950
shale	2025
shale & shells	2325
salt & shale	2425
shale & shells	2535
shale & lime	2590
lime	2655
shale & shells	3065
lime & shale	3165
shale & shells	3265
lime	3395
lime & shale	3510
lime	3765
lime & shale	3805
lime	3945
lime cherty	3960
lime	3983
chert	3990
lime	3995
lime & shale	4040
lime	4294
chert	4302
shale	4305
shale & lime	4485
lime	4501
chert & lime	4506
lime	4546
4546 equals 4537 1/2 Corr.	
lime	4564
Total Depth.	

Tops: Anhydrite	1925
Fl. Flint	2785
Base Fl. Flint	2890
Neva	3125
Howard	3485
Topeka	3615
Lansing	3945
Base K.C.	4200
Miss. 4538=28 1/2 SICorr.	