

KANSAS DRILLERS LOG

State Geological Survey
WICHITA BRANCH

S. 23 T. 16S R. 25W ^E/_W

API No. 15 — 135 — 21,719
County Number

Loc. Approx. SE NW NW

Operator
Kansas Petroleum, Inc.

County NESS

Address
Suite 100, 200 East First Street

Well No. 1 Lease Name HUXMAN


Footage Location
1320 feet from (N) (X) line 990 feet from (W) line

Principal Contractor Husky Drilling Co., Inc. Geologist Walter I. Phillips

Spud Date November 7, 1979 Total Depth 4595 P.B.T.D.

Date Completed November 14, 1979 Oil Purchaser

640 Acres
N



Locate well correctly

Elev.: Gr. 2572

DF 2574 KB 2577

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8		331	60-40 Pozmix	200	2% Gel 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
D & A					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
 Kansas Petroleum, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS,
 DRY HOLE, SWDW, ETC.:
 Dry Hole

Well No. 1 Lease Name HUXMAN

S 23 T 16S R 25W E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Formation Tops (KB 2577)				
Anhydrite	1957	+ 620		
Heebner	3916	-1339		
Lansing	3955	-1378		
Base Kansas City	4259	-1682		
Fort Scott	4462	-1885		
Mississippi	4572	-1995		
RTD	4595	-2018		
DST #1 4430-4595 Open 30 minutes, closed 30 minutes, open 30 minutes, closed 30 minutes. Weak blow. Recovered 15' mud.				
IFP 93#-103#	IBHP	932#		
FFP 113#-112#	FBHP	783#		
HYD 2271#-2262#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	PRESIDENT
	Title
	November 23, 1981
	Date

MICHAEL BUSHNICH
 2-1-1981