

25-16-25W

COMPANY STERLING DRILLING, ETAL

SEC. 25 T. 16 R. 25W
LOC. C NW SW

FARM Flax

NO. 1

TOTAL DEPTH 1986

COMM. 1-24-67

COMP. 1-26-67


SHOT OR TREATED

CONTRACTOR Sterling Drlg.

ISSUED 3-11-67

COUNTY Ness

KANSAS



CASING

20	10
15	8
12	6
13	5

ELEVATION 2553

PRODUCTION DRY (ANHY)

FIGURES INDICATE BOTTOM OF FORMATIONS

ROTARY TOTAL DEPTH: 1986'

LOG

CASING RECORD

0 - 180	Sand & Clay
180 - 320	Clay & Shale
320 - 1700	Shale & Sand
1700 - 1916	Shale
1916 - 1948	Anhydrite
1948 - 1986	Shale T.D.

Plugged with 50 sacks HA-5 at 1635' through drill pipe; 150 sacks 50-50 Pozmix #1 with 4% gel at 1535'; 150 sacks 50-50 Pozmix #1 with 4% gel from 450' to surface. Completed at 3:45 p.m. by Howco. Plugger, Leo Massey.

TOS: SCOUT

Anhydrite	1916
Base Anhydrite	1948