

WELL RECORD

State Geological Survey
WICHITA, BRANCH
12-28-17E

WELL No.: C 64 FARM; Kepley OPERATOR; B.P.I.

LOCATION; 12 - 28S - 17E

ELEVATION: _____ STATE: Kansas COUNTY: Neosho

DRILLING CONTRACTOR: Circle W Drilling Inc. RIG #: 1

PRODUCTION FORMATION: _____ TOP: _____ BOTTOM: _____

PERFORATED: _____

TOTAL DEPTH: 1328' HOLE SIZE: 6 1/2"

CASING DETAILS: Set 40' of 7" 20# Surface casing.

PUMP EQUIPMENT: _____

RODS & PUMP: _____

Thick ness	FORMATION	Depth	Thick ness	FORMATION	Depth
6'	Soil & Clay	6'	15'	Lime	614'
6'	Shale	12'	7'	Shale	621'
4'	Lime	16'	6'	Lime	627'
71'	Shale	87'	138'	Shale	765'
3'	Lime	90'	27'	Sand & Shale	792'
34'	Shale	124'	9'	Oil Sand - Fair Show	801'
2'	Lime	126'	1'	Coal	802'
4'	Shale	130'	12'	Shale	814'
51'	Lime	181'	50'	Sand & Shale - light odour	864'
58'	Shale	239'	3'	Coal	867'
11'	Lime	250'	3'	Sand & Shale	870'
15'	Shale	265'	165'	Shale & Sand	1035'
6'	Lime	271'	14'	Shale	1049'
9'	Shale	220'	3'	Coal & Shale	1052'
44'	Lime	324'	151'	Lime (Top Lime 1064')	1203'
27'	Shale	351'	13'	Lime - gas Show	1216'
2'	Lime	353'	5'	Lime	1221'
67'	Shale with Lime breaks	420'	4'	Lime - show gas	1225'
14'	Lime	434'		Lime	T.D. 1328'
69'	Shale & Clay w/ Lime brks	500'			
8'	Lime	508'			
4'	Shale & Coal	512'			
43'	Lime	555'			
4'	Coal	559'			
40'	Shale	599'			