

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


Company - SOHIO PETRO. CO.
Farm Drake No. 2

SEC. 26 T. 16 R. 25 W
CNE NW

Total Depth. 4557'
Comm. 11-16-45 Comp. 12-30-45
Shot or Treated.
Contractor.
issued. 5-11-46

County. Ness

KANSAS



CASING:
10 3/4" 320.17' DF

Elevation. 2559

Production. Dry

Figures Indicate Bottom of Formations.

| | |
|----------------|------|
| clay | 0-40 |
| sand & gravel | 150 |
| shale & shells | 375 |
| shale | 650 |
| shale & shells | 1065 |
| shale & lime | 1300 |
| anhydrite | 1330 |
| shale & lime | 1365 |
| shale & shells | 2005 |
| lime | 2045 |
| shale & lime | 2500 |
| lime | 2770 |
| shale | 2815 |
| lime | 2855 |
| lime hrd | 2915 |
| lime | 2960 |
| lime hrd | 3025 |
| lime | 3060 |
| lime brkn | 3155 |
| lime | 3368 |
| shale & lime | 3510 |
| shale & shells | 3550 |
| shale | 3765 |
| shale & lime | 3915 |
| lime | 4005 |
| lime brkn | 4060 |
| lime | 4180 |
| lime hrd wh | 4210 |
| lime | 4350 |
| lime brkn | 4380 |
| lime & shale | 4405 |
| shale | 4430 |
| lime | 4520 |
| lime & chert | 4530 |
| lime | 4557 |

Total Depth.

Tops:
Leebner shale 3870
Lans.- K.C. 3913
Conglomerate 4502
Mississippian 4539
Mississippian
Dolomite 4549

3910
2559
-1351

4539
2559
-1980

Hole Plugged 12-30-45.
Bottom of surface pipe 12
sacks of cement. Top of
surface to 20'. Below
btm of cellar w/11 sacks
Lone Star Cement.

Plugged & abandoned 12-31-45.
No commercial oil or gas shows
from top of hole to btm. No
electric log run.