

27-16-25W

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CHIEF DRILLING

SEC. 27 T. 16 R. 25W

FARM Conkright NO. 1


LOC. C SW NW

TOTAL DEPTH 4520'

COUNTY Ness

COMM. 9-17-68

COMP. 9-27-68



SHOT OR TREATED

CONTRACTOR Chief Drilling

ISSUED 10-26-68

CASING

20	10	
15	8	5/8" 309' cem w/ 200 sx
12	6	
13	5	

ELEVATION 2550' KB

PRODUCTION DRY/MISS

FIGURES INDICATE BOTTOM OF FORMATIONS

2545 Gr.  
2547 D.F.  
2550 K.B.

Clay	0	50
Shale and Sand Streaks	50	309
Shale	309	485
Shale & Sand Streaks, Hard Sand	485	1210
Shale & Red Bed	1210	1385
Sand	1385	1630
Shale, Red Bed, Shells and Sand Streaks	1630	1913
Anhydrite	1913	1942
Shale	1942	2150
Shale & Shells	2150	2490
Shale, Lime & Hard Sand	2490	2555
Shale & Lime	2555	2834
Lime	2834	2960
Lime & Shale	2960	4060
Lime	4060	4212
Lime & Shale	4212	4420
Lime	4420	4490
Cherty Lime	4490	4500
Shale, Lime & Chert	4500	4515
Mississippi Chert	4514	4520

FORMATION TOPS

Anhydrite	1913	+ 637
Heebner	3845	-1295
Lansing-Kansas City	3883	-1333
Fort Scott	4397	-1847
Conglomerate	4472	-1922
Mississippian	4492	-1942
Total Depth	4520	-1970