

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

27-16-25W

Company- BENNETT & ROBERTS OIL OPERATIONS
Farm- Burrell No. 1

SEC. 27 T. 16 R. 25W
NE NE SW

Total Depth. 4500'
Comm. 6-3-57 Comp. 6-21-57
Shot or Treated.
Contractor. Bennett & Roberts Oil Operations
Issued. 2-22-58

County Ness
KANSAS



CASING:
8 5/8" 284' cem w/175 sx
5 1/2" 4400' cem w/125 sx

Elevation. 2534' D. F.

Production. 25 BOPD & WTR.

Figures indicate Bottom of Formations.

surface soil & clay	40
sand	60
sand & shale	234
shale	820
sand & shale	910
shale, shells & red bed	1250
shale & shells	1390
sand	1420
red bed	1900
Anhydrite	1945
shale & shells	2250
shale & lime	2280
shale & shells	2515
shale & lime	2870
shale & lime, streaks	2910
lime	3090
shale & lime	3904
lime	4302
lime & shale	4390
lime	4490
Cherty lime	4500
Total Depth	

<u>TOPS:</u>	<u>SAMPLE</u>	<u>ELECTRIC</u>
Heebner	3845	3855
Lansing	3883	3892
Fort Scott	4392	4401
Conglomerate	4421	4431
Mississippi	4488	4487

D.S.T. #1, (By Halliburton Measurements)
4488-4510, packer set at
4488, open one hour, good
blow immediately slowly de-
creasing toward end of test,
recovered 1530' fluid, being
1050' clean of oil, 480'
frothy oil. I.F.P. 155#,
F.F.P. 645#, F.B.H.P. 950#
in 20 minutes, still rising.