

28-16-25W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- KERN DRILLING CO.
Farm- Hanlin No. 1

SEC. 28 T. 16 R. 25W
150' NW of C SW SW

Total Depth. 4498'
Comm. 8-16-61 Comp. 8-30-61
Shot or Treated.
Contractor. Hellar Drilg. Co.
Issued. 12-23-61

County Ness KANSAS



Elevation. 2553' RB

Production. 192 BOPD

CASING:

8 5/8" 302' cem w/225 sx.
4 1/2" 4498' cem w/150 sx.

Figures Indicate Bottom of Formations.

clay, sand, shale	150	
shale, clay	255	
shale	440	
shale, sand	1302	
Blaine Anhydrite	1315	
shale	1440	
shale, red bed	1893	
Cimarron Anhydrite	1930	
shale	2510	
shale, lime	2805	
lime, shale	2950	
shale, lime	3120	
lime, shale	3264	
shale, lime	3405	
lime, shale	3375	
shale, lime	3700	
lime, shale	3810	
Lansing-Kansas City	3850	
lime	3995	
Lansing-Kansas City	4053	
lime	4366	
shale, Ft. Scott	4380	
shaly lime	4400	
lime	4414	
lime, chert	4492	
Mississippian	4498	RTD
Total Depth		

TOPS: SCOUT

Blaine	1302
Cimarron	1912
Heebner	3822
Toronto	3834
Lansing	3854
Ft. Scott	4372
Mississippi	4470
Mississippi Dolomite	4487