

WICHITA, BRANCH


API No. 15 — 135 — 20,742
County Number

S. 28 T. 16 R. 25
W

Loc. A/C SW SE

County Ness

640 Acres
N



Locate well correctly

Elev.: Gr. 2534

DF _____ KB 2539

Operator
Palomino Petroleum

Address 304 Insurance Building
Wichita, Kansas 67202

Well No. #2 Lease Name Sloan

Footage Location
App. 660 feet from XX (S) line App. 660 feet from XXX (W) line

Principal Contractor Hellar Drilling Co., Inc. Geologist Robert LaRue

Spud Date April 17, 1973 Total Depth 4525 P.B.T.D. -----

Date Completed April 27, 1973 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24	224'	Regular Portland	175	Calcium Chloride (Halco) - 2%

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Operator

PALOMINO PETROLEUM

D/A

Well No.

2

Lease Name

Sloan

28 T 16 R 25 ^{XX} W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand & Shale	0	224		
Shale	224	560		
Shale & Red Bed	560	910		
Sand & Shale & Red Bed	910	1278		
Blaine-Anhydrite	1278	1285		
Shale & Red Bed	1285	1762		
Shale	1762	1880		
Anhydrite	1880	1919		
Shale	1919	1995		
Shale & Salt Section	1995	2470		
Shale & Lime	2470	2635		
Lime & Shale	2635	2990	Ft. Riley	
Shale & Lime	2990	3180		
Lime & Shale	3180	3513		
Shale & Lime	3513	3680		
Lime & Shale	3680	3685	Heebner	3823
	3685	3917	L.K.C.	3864
Lime	3917	4060		
Lime	4060	4180	L.K.C.	
Lime	4180	4364	Pawnee	4300
	4364	4390	Ft. Scott	4367
Lime	4390	4465	Cherokee	
Lime	4465	4495		
	4495	4505	Mississippian	4472
Lime	4505	4515		
	4515	4525	Miss.	
			RTD	4525
NO LOG RUN				

USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.



R. W. Watchous
 R. W. Watchous Signature

Owner, PALOMINO PETROLEUM

May 4, 1973

Date