

P1  
D R I L L E R S    L O G

Ind  
28-16-25W



#2 McClean

CASING RECORD: 7 jts. new 24# 8-5/8" surface casing  
COMPANY: Palomino Petroleum  
CONTRACTOR: Strata Drilling Company  
COMMENCED: May 4, 1981  
COMPLETED: May 10, 1981  
DESCRIPTION: NW SE NE Section 28-16S-25W Ness County, Kansas  
ELEVATION: 2570' KB  
TOTAL ROTARY DEPTH: 4520'

---

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale, sand	0	290	Ran 280' new 24# 8-5/8" surface casing; set and cemented at 285' with 180 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 1:30 a.m., May 5, 1981.
Shale, sand	290	1927	
Anhydrite	1927	1960	
Shale	1960	2520	
Lime and shale	2520	4520	

Run 120 jts. new 14# casing, set at 4519' with 100 sacks Halliburton Lite, 100 sacks 60-40 pozmix, 10% salt. Plug down at 8:20 p.m., May 10, 1981.

---

STATE OF KANSAS )  
                          )ss  
COUNTY OF BARTON)

I certify that the above is a true and correct copy of the log to the best of my knowledge.

STRATA DRILLING COMPANY

*Charles W. Steincamp*  
Charles W. Steincamp

Sworn to and subscribed before me this 19th day of May, 1981.