

29-16-25W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. KERN DRILLING CO., INC.
Farm- Burgess No. 2

SEC. 29 T. 16 R. 25W
150' SE of C NW SE

Total Depth. 4507'

Comm. 9-2-61

Comp. 9-15-61


County Ness

KANSAS

Shot or Treated.

Contractor. Hellar Drlg. Co.

Issued. 12-30-61



CASING:

8 5/8" 306' cem w/275 sx.
4 1/2" 4489' cem w/150 sx.

Elevation. 2551'

Production. 107 BOPD

Figures Indicate Bottom of Formations.

surface sand	41
sandy clay	245
blue shale	306
shale & sand	696
shale, shells, red bed	1314
Blaine Anhydrite	1330
red bed & sand	1740
red bed	1923
Cimarron Anhydrite	1956
shale	2347
shale & lime	2785
lime & shale	2903
lime	2950
lime, shale	3029
shale, lime	3210
sandy shale, lime	3278
lime, shale	3488
Topeka lime	3279
shale, lime	3712
lime, shale	3811
Lansing-Kansas City	3856
lime	4251
lime & Conglomerate	4286
lime	4376
shale	4439
lime	4507 RTD
Total Depth	

TOPS: SCOUT

Blaine	1314
Cimarron Anhydrite	1922
Ft. Scott	4380
Mississippi	4480