

15-135-21190

OPERATOR: Moble C. Hoover
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: GULICK #3
LOCATION: NW SW Section 29-16S-25W
Ness County, Kansas
SPUD DATE: April 16, 1976
COMPLETION DATE: April 24, 1976

0	71	Surface Clay & Sand
71	265	Sand & clay
265	319	Sand
319	2020	Sand & shells
2020	2144	Sand & shale
2144	3174	Shale
3174	3390	Shale & Lime
3390	3620	Shale
3620	4055	Shale & Lime
4055	4315	Lime & Shale
4315	4405	Lime
4405	4522	Lime, Shale & chert
4522	4528	Mississippian
	4528	Rotary Total Depth

Drilled 252' of 12 $\frac{1}{4}$ " hole. Ran 6 jts. casing, Set @ 265'. Cemented with 200 sx. Common Cement, 2% gel, 3% ca. cl. Cement did circulate. Plug was down @ 8:30 p.m. April 16, 1976.

Ran 136 jts. of 4 $\frac{1}{2}$ " - 10 $\frac{1}{2}$ #, Set @ 4519'. Tallied 4519'. Cemented with 200 sx. 50/50 Posmix, 3% gel, 2% ca. cl. Plug was down @ 3:30 p.m. April 24, 1976.

SAMPLE TOPS:

Anhydrite 1950'
B/Anhydrite 1980'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the GULICK #3, NW SW Section 29-16S-25W Ness County, Kansas.

ABERCROMBIE DRILLING, INC.

By: 
Jerry A. Langrehr-Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 29th day of April, 1976.