

State

Kansas

County

Barton

Company

Brimingham-Bartlett
Oil Co.

Well No.

1

Farm

Monty

Survey

Block No.

Sec.

5

Twp.

18⁶


Range

14^W

Co-Ord.

Elev.

1940 RB



10 H. M. - #1250.00

40% - Lehigh

12.5% - Dale Carnegie

31.09375% - Wm. Lehigh Oil Co.

11.71875% - Roger L. Measner

4.6875% - C. B. Kinkaid

NOTE: Show Sketch of Lease and Well Location in Above Space

990

Ft. from N. Line

Ft. from S. Line

2310

Ft. from W. Line

Ft. from E. Line

Date	Depth	
9-10-56		8 5/8" @ 605' w/ 325 ex cem. P.D. 9:30 A.M. 9-10-56
9-11-56	935'	Drilg.
9-13-56	2250'	Drilg.
9-14-56	2745'	Drilg.
9-15-56	2970'	Drilg.
9-16-56	3130'	Drilg.
9-17-56	3211'	Drilg.
		Hebner 3111 (-1174)

Date	Depth	717698
		Brown Line 3174 (-1234)
		Lansing 3186 (-1246)
	DST #1	3180-96, of 1 hr. gas to sur. 14"
		Rec 540' oil, 15' SW BHP 1000 #
	DST #2	3197-3211 of 1 hr. rec. 330' SW BHP
		930 #
9-18	3285'	drly.
	DST #3	3263-85 of 1 hr. rec. 60' watery
		mud. BHP 740 #. Expect to
		reach Arbuckle tonight.
9-19		Arbuckle 3445 (-1504)
		TD 3453' Oryzomys
9-24		♀ in today
		Set 5 1/2" @ 3448' w/100
		ex. cem. 3453 TD
9-26		Drilled plug. Deepened to
		3458'. ^{Sub} Tested 29 BOPH.
		Cemented back to 3282' P.D.
		Perf. 3185-90 w/20 shots
		110' oil/10" Bailed 2 1/2 hrs
		✓ 30". 500 gal. acid sub.
		11 BOPH/NW, sub. 1800'
		off bottom. Prep to run
		tubing to put on pump.
		Pch. 50 BOPD