


State Kansas County Leano
 Company Fairchild Copher Well No. 1
 Farm Jones 'A'
 Survey

Block No. Sec. 15 Twp. 26^s Range 9^w
 Co-Ord. Elev. 1691 KIB
1686 LI.



Contr. - Dabbert Jones
 * Farmout (checkered)
100% - Fairchild Copher
Bed. - Jim Pierre
3350' ls. Kc test to
be com. within
90 days from comp -
of Fairchild - Leano.

NOTE: Show Sketch of Lease and Well Location in Above Space

* I own reef to B. & Kc.
 Ft. from N. Line Orl. John S. Miller Jr. Ft. from S. Line

Ft. from W. Line Ft. from E. Line


Date	Depth	
7-7-86		M.S.R. 9 - Speed - 8 5/8" (289 (7 its. new) w/ 225 sq cem (60-40 per) 270 gal, 370. cc. (Cement) did not cure P.D. @ 9:45 a.m. 7/8/86 Pumped 1" am. to 30' allow the reef w/ 60 sq cem. (60-40 per) 270 gal 370. cc

Date	Depth	
		717713
		P.H. @ 10:15 a.m. 7/8/86
7/9	1363	deleg. (bit trip.)
7/10	2015	deleg.
7/11	2643	deleg.
	2240	Orange shale (-549)
	2368	Langdon sd. (-677)
		Frost Cone sd.
	2782	Japp's m (-1091)
	3159	H&L sh (-1468)
	3357	Ls. (-1666)
7/12	3220	deleg.
		D.L. #1 - 3386-3414 - 45-60-60-90
		wb. bl deleg. to string below
		rec 270' grip, 150' sec
		0.8 cm (3% oil)
		ifp. 31-52, ifp. 62-83 [#]
		rip 1236-1236
		hydrilate 1599-1599 [#]
		Temp 108°
7/13	3414	(Testing)
		D.L. #2 - 3432-56-30-45-45-60
		wb. blow through part,
		rec. 90' mud (rec. oil)
		60' mud wt, 46,000 psi/mud
		ifp - 41-52, ifp 72-83 [#]
		rip - 1251-1236, hydrilate 1651-
		Temp 109°

State Kansas County Lea
Company Schenck Explorer Well No. 1
Farm James A
Survey

Block No. Sec. 15 Twp. 26 Range 9

Co-Ord. Elev. 1691 KB
1686 ft.



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth
7/14	3555 (Testing)
	D.S.P. #3 - 3523-55-45-60-45-60
	strong blow (no gas)
	Rec. 830' gip, 10' or less
	(7% oil) D.P. - 41-41
	D.P. - 41-41, dip 208-312
	hydrostatic 1682-1682
	3710 G.D. (Logging hole)
	R.O.A. 7-15-86
	(over) for plugging info)

Date

Depth

717713

Log Taps

2236 Anaga Shale (-545)

2365 Langdon S.L. (-674)

2782 Tapeha Lime (-1091)

3161 Heebner Sh. (-1470)

3359 Lansing (-1668)

(did not penetrate Base of K.C.)

Plugging:1st plug @ 1500' w/35# (60-40^{res})2nd plug @ 350' w/35# (67oz^l)

3rd plug @ 60' w/25#

10 # in set hole

Completed - 7:30 P.M. 7/15/86

State Plugging (Sander)
by B.D. mud