

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

APR 23 1932

22-32-4E


Location. NE S¹/₄ NE 940 WL 884¹/₂ SL NE¹/₂ Blk 12 Lot 5

Sec. 22 T. 32 R. 4E

Casing Record..

County.. Cowley.

10" 1734 Farm.. Dibbins No. 2
 20" 8" 2338 Company.. Sinclair-Prairie Oil Co.
 15 1/2" 427 65/8" 2588 Contr..
 12 1/2" 1128 53/16" 3238 Comm. 2-7-32 Comp. 4-18-32



Total Depth. 3262 Shot.. Quarts Between..
 Correspondence Regarding This Well Should Be Referred To..

Figures Indicate Bottom of Formations.
 Date Issued. 4-23-32

Elevation..
 Initial Production.
 Swabbed 706 bbls 21 hrs.
 Pumped 532 1/2 bbls in 24 hrs.

Formation	Depth	Formation	Depth	Formation	Depth.
cellar	8	shale	1098	lime	2290
clay yellow	15	lime	1132	sand	2313
lime	60	shale	1198	sdv lime	2316
broken lime	70	1/2 BW 1230		slate	2320
slate	75	lime	1250	sand	2335
sdv lime	115	shale	1260	shale sdv	2350
shale blue	120	lime shells	1285	show oil 2354-2385	
red rock	125	lime white	1305	sand	2397
lime	135	shale shells	1315	slate	2450
shale blue	140	lime shells	1320	shale	2455
lime	145	slate	1325	lime hard	2505
shale	150	lime	1327	sand water	2510
lime	155	shale	1340	lime white	2540
red rock	165	lime	1380	lime blk	2555
sdv lime	205	shale blk	1386	shale	2565
shale blue	210	lime shells	1389	lime	2575
red rock	225	shale	1395	shale	2640
lime	240	lime shells	1398	lime	2650
shale	245	slate	1410	shale shells	2685
lime hard	265	1/2 BW 1415		lime hard	2717
lime	280	sand broken	1430	shale	2725
shale blue	290	shale blue	1450	lime hard	2750
lime	310	lime	1455		
shale	320	2 BW 1460		shale	2815
lime white 5BW 340	350	sdv lime	1475	shale shells	2840
red rock	370	lime white	1480	lime gritty	2850
shale light	382	sdv lime	1500	shale blue	2875
lime	385	lime white	1535	red rock	2879
red rock	395	shale blue caving.	1572	shale	2895
lime	430	lime	1578	3/4 M gas 2900-30	
shale blue	460	shale blk	1583	sand	2955
lime	465	shale blue	1600	chat	2957
shale blue	475	shale grey	1608	lime grey	3010
lime hard	525	red rock	1611	lime	3060
shale blue	533	shale blue	1635	lime blk	3130
lime	535	lime	1650	lime white	3145
shale blue	545	shale grey	1675	shale green	3163
lime	570	3 BW 1690		lime white	3176
shale	575	sand broken	1695	shale blk	3251
lime	580	lime	1712	sand	3262 T.D.
shale blue	590	shale blue	1735	more oil 3260-62	
shale light	595	lime sdv	1739		
shale blue	650	shale blue	1760		
lime	655	sdv shale	1765		
shale light	665	shale blue	1795		
lime	670	sdv shale	1845		
lime	775	lime	1850		
lime blk	780	shale	1872		
shale	898	sand	1885		
bailing water 910-30		5 BWPHR 1872-85			
sand grey	935	broken lime sdv	1935		
sand	947	broken lime	1940		
shale	975	sand water	1980		
lime	980	HFW 1950-60			
red rock	985	sdv lime	2010		
shale	1022	shale blue	2060		
lime blk hard	1030	lime blk hard	2065		
shale	1065	shale blue	2075		
lime	1070	sand	2100		
shale	1075	shale blue	2278		
lime	1094	Drilling hole wet.			

3176 3751
 2955 3176
 221 75