

29-16-25W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- KERN DRILLING CO., INC.  
Farm- McLean No. 2

SEC. 29 T. 16 R. 25W  
C NE NE

Total Depth. 4520'  
Comm. 8-27-62 Comp. 9-6-62  
Shot or Treated.  
Contractor. Hellar Drilling Co., Inc.  
Issued. 1-26-63

County Ness  
KANSAS



CASING:  
8 5/8" 290' cem w/215 sx.  
4 1/2" 4506' cem w/250 sx.

Elevation. 2575' RB

Production. 101 BOPD, NW

Figures indicate Bottom of Formations.

|                             |          |
|-----------------------------|----------|
| surface sand                | 90       |
| sand-shells                 | 178      |
| shale-limey shale           | 290      |
| shale-sand                  | 940      |
| shale-sand-shells           | 1337     |
| Blaine-anhydrite            | 1351     |
| shale-sand-shells           | 1700     |
| shale-red bed               | 1942     |
| Cimmaron                    | 1974     |
| shale-red beds              | 2060     |
| shale-salt section          | 2340     |
| shale-lime                  | 2864     |
| lime & shale                | 3260     |
| shale & lime                | 3700     |
| lime & shale                | 3939     |
| lime (Kansas City)          | 4059     |
| lime                        | 4410     |
| shale & lime                | 4483     |
| lime & shale                | 4505     |
| core #1 - reaming core hole | 4520 RTD |
| Total Depth                 |          |

|                    |             |
|--------------------|-------------|
| TOPS: SAMPLE       |             |
| Blaine             | 1337 - 1351 |
| Cimmaron Anhydrite | 1942 - 1974 |
| Heebner            | 3852        |
| Lansing            | 3891        |
| Base Kansas City   | 4182        |
| Fort Scott         | 4400        |
| Mississippian      | 4506        |