

29-16-25W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- KERN DRILLING CO., INC.
Farm- McLean No. 3

SEC. 29 T. 16 R. 25W
C SE NE

Total Depth. 4503'

Comm. 11-7-62

Comp. 11-19-62


Shot or Treated.

Contractor. Hellar Drilling Co., Inc.

Issued. 3-9-63

County Ness

KANSAS



Elevation. 2556' RB

Production. 83 BOPD, NW

CASING:

8 5/8" 292' cem w/215 sx.

4 1/2" 4490' cem w/250 sx.

Figures Indicate Bottom of Formations.

shale, sand	292
cement red bed	329
sand & shale	1319
Blaine	1344
sand & shale	1743
shale-shales	2104
sand, shale & shells	2460
shale & lime	2625
lime	2822
Fort Riley section	2930
shale & lime	3109
lime & shale	3341
chalky lime & shale	3520
shale & lime - "chalky"	3779
shale & lime	3868
lime & shale	3936
Kansas City	3975
shale & lime	4015
lime (chert)	4109
lime	4380
Fort Scott	4388
lime	4490
core #1	4503 RTD
Total Depth	

TOPS: LOG

Blaine	1319	-	1340
Cimmaron Anhydrite	1933	-	1964
Heebner	3831		
Toronto	3846		
Lansing	3870		
Fort Scott	4385		
Mississippi	4488		