

CONTRACTOR'S WELL LOG

State Geological Survey
WICHITA, BRANCH

32-16-25W

OPERATOR:
 CONTRACTOR:
 WELL NAME:
 LOCATION:
 SPUD DATE:
 COMPLETION DATE:

Moble C. Hoover
 Abercrombie Drilling, Inc.
 LILLIE #2
 C NW NE Section 32-16S-25W
 Ness County, Kansas
 May 10, 1976
 May 20, 1976

15-101-20, 174

0	150	Sand & Rock
150	445	Shale
445	1112	Surface Shale & Red Beds
1112	1995	Sand & Shale
1995	2230	Shale
2230	2834	Shale & Lime
2834	3000	Shale
2834	3315	Lime & Shale
3315	3520	Shale
3520	3735	Shale & Lime
3735	3925	Lime & Shale
3925	4072	Shale
4072	4138	Shale & Lime
4138	4210	Lime
4210	4290	Lime & Shale
4290	4354	Shale & lime
4354	4404	Lime
4404	4438	Shale
4438	4493	Lime
	4493	Rotary Total Depth

Drilled 264' of 12 $\frac{1}{4}$ " hole. Ran 6 jts. 8 5/8" casing, Set @ 252'. Cemented with 175 sx. cement, 2% gel, 3% ca.cl. Cement did Circ. Plug was down @ 8:00 p.m. May 10, 1976.

Ran 135 jts. 4 $\frac{1}{2}$ " casing, 10 $\frac{1}{2}$ "#. Went to bottom then picked up 16' and set @ 4477'. Cemented with 200 sx. 50/50 Posmix, 2% ca.cl. Job completed @ 1:00 a.m. May 20, 1976.

SAMPLE TOPS:

Anhydrite 1904'
 B/Anhydrite 1924'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Lillie #2, C NW NE Section 32-16S-25W Ness County, Kansas.



ABERCROMBIE DRILLING, INC.