

32-16-25W  
V


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. ROBERTS & MURPHY  
Farm. Burgess No. 1

SEC. 32 T. 16 R. 25W  
C NE NW

Total Depth. 4522'  
Comm. 11-4-61 Comp. 11-21-61  
Shot or Treated.  
Contractor. Hellar Drlg. Co.  
Issued. 3-24-62

County Ness KANSAS



CASING:

8 5/8" 304' cem w/215 sx.  
4 1/2" 4513' cem w/250 sx.

Elevation. 2576' RB

Production. 109 BOPD

Figures Indicate Bottom of Formations.

clay, sand, gravel	200
clay, blue shale	304
shale, sand	1759
shale	1937
Anhydrite	1970
shale	2466
Ft. Riley	2566
lime	2717
lime & shale	2934
shale, lime	3025
lime, shale	3165
shale, lime	3330
lime, shale	3465
Howard lime	3562
lime, shale	3897
lime	4140
Lansing-Kansas City	4230
lime	4336
shale, lime	4426
Ft. Scott	4449
lime, shale	4522 RTD
Total Depth	

TOPS: SCOUT

Blaine	1318
Cimarron Anhydrite	1938
Howard Lime	3422
Heebner	3846
Toronto	3863
Lansing	3883
Fort Scott	4396
Mississippi	4510