

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


32-16-25W

Company. ROBERTS & MURPHY  
Farm. Burgess No. 2

SEC. 32 T. 16 R. 25W  
150' N C SE NW

Total Depth. 4508'  
Comm. 8-9-62 Comp. 8-22-62  
Shot or Treated.  
Contractor. Hellar Drilling Co., Inc.  
Issued. 12-22-62

County Ness  
KANSAS



CASING:  
8 5/8" 293' cem w/215 sx.  
5" 4508'

Elevation. 2564' RB

Production. 48 BOPD, NW

Figures Indicate Bottom of Formations.

shale-sand-shell	274
shale	292
shale-shells-sand	750
shale-sand	1312
Blaine-anhydrite	1326
shale	1380
shale-red beds	1921
Cimmaron-anhydrite	1954
shale	1983
shale & lime	2290
shale & salt solution	2440
shale-lime	2560
Fort Riley	2755
lime	2988
shale & lime	3237
lime & shale	3367
shale & lime	3465
shale & lime (chalky)	3612
lime & shale	3830
lime	4034
Lansing-Kansas City	4085
lime	4170
lime & shale	4299
lime	4370
ream rat hole	4375
ream core hole	4400
lime-shale	4455
ream core hole	4477
core #3	4508 RTD
Total Depth	

TOPS: LOG

Blaine	1312
Anhydrite	1921
Topeka	3556
Heebner	3820
Toronto	3842
Lansing	3861
Base Kansas City	4144
Fort Scott	4372
Mississippi Spergeon	4466
Mississippi Warsaw	4481