

32-16-25W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- J. M. HUBER CORP.
Farm- Lewis No. 1

SEC. 32 T. 16 R. 25W
C NW NW

Total Depth. 4536'
Comm. 5-4-62 Comp. 5-17-62
Shot or Treated.
Contractor. Hellar Drilling Co., Inc.
Issued. 10-6-62

County Ness
KANSAS



Elevation. 2557' DF

Production. 115 BOPD, 23% WTR

CASING:
8 5/8" 297' cem w/225 sx.
4 1/2" 4535' cem w/150 sx.

Figures Indicate Bottom of Formations.

sand, shale	250
shale	297
shale, sand, red bed	1309
Blaine anhydrite	1322
red bed	1435
sand, shale	1760
shale, red bed	1919
Cimmaron anhydrite	1949
shale	2292
salt section	2471
lime, shale	2760
shale, lime	2770
lime, shale	3247
shale, lime	3563
shale, lime, chalk	3732
lime, shale	3784
shale, lime	3860
lime	3945
Lansing-Kansas City	4045
lime	4169
lime, shale	4255
lime	4370
lime, shale streaks	4410
lime, shale, chert	4462
lime, chert	4473
core #1	4493
core #2	4505
core #3	4535 RTD
core #3 ?	4536
Total Depth	
TOPS: LOG	
Base Heebner	3847
Lansing	3868
Ft. Scott	4396
Mississippi Spurgeon	4490