


Company - MOSBACHER ET AL
 Farm - Sloan No. 1.

SEC. 16 T. 9 R. 22 E
 SWc NE

16-9-22E

County. Leavenworth
 KANSAS



Total Depth. 1468
 Comm. 8-25-44 Comp. 10-6?-44
 Shot or Treated.
 Contractor. S. R. McKinney
 Issued. 4-28-45

Plotted

CASING:
 10" 56' 6 5/8" UR roset 1190' Elevation. 959ft
 8" 673' SIM 5" 1294' SIM
 7" 1030' SIM @ 1058' Production. Dry

Figures Indicate Bottom of Formations.



toil	0-2	shale drk	998
clay	33	sand	1012
sand water	35	shale	1016
shale	45	lime	1020
lime	50	shale	1022
10" @ 56 little wtr under pipe		sand HFW	1032
shale	175	shale drk	1070
lime	195	shale gy sdy	1142
shale	198	sand (HFW @ 1145)	1175
lime	205	shale blk	1192
shale	224	shale lgt	1200
lime	249	shale blk	1262
shale	266	wtr 1240-50 8 BPH	
lime	281	sand	1290
shale	320	lime	1294
lime	339	shale wh	1297
shale	341	lime & shale, shale	
lime	347	lgt to green	1325 - m
shale	350	lime & chert (Miss. 1325)	1354
lime	351	lime	1468
shale	355	hole making 1 BWPH	
lime	371	Total Depth	
shale	381		
lime	391		
shale	408		
lime	452		
shale drk	457		
lime	479		
shale drk	482		
lime	484		
shale gy	486		
lime Hertha	500		
shale gy	605		
sand	610		
shale lgt	620		
lime	630		
shale yellow & green			
sandy	640		
lime shells	652		
shale lgt	666		
lime	670		
shale drk	687		
lime	692		
shale gy	711		
lime	715		
shale drk	721		
lime shells	730		
shale blue	737		
shale	739		
lime	742		
	746		
	755		
		shale	825
		shale gy sdy	900
		lime	902
		shale drk	925
		sand (water 4 -	950
		shale drk bailers wtr	966
		shale sdy lgt	980

McLouth sand 1272-1290

959
 459

 500

