

State

Kansas

County

Martin

Company

P. E. P. L. Co.

Well No.

1-21

Farm

Behm

Survey

Block No.

Sec.

21

Twp.

31^u

Range


41^w

Co-Ord.

Elev.

3410 RB

C. SW/4



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date

Depth

8" @ 2297

D.L.J. #1

(failed) 5205-56

Cased 5205-56

gas, drill pipe

9-29

D.L.J. #2

5207-56 - Op. 75"

Rev. 1890' gas

235 gun, 95' d. gun

ZP. - 150-190 50

BHP. - 1100# - 20"

5265

Only

Date	Depth	717918
10.8.2. #3	5254-75	Op. 1 hr.
		Rev. 990' ge mly SW.
		B.H.P. - 1310 [#]
	5275	Dily.
10.8.2. #4	5348-70	Op. 80", rev.
		30' stly mud, 990' SW
		BHP - 1450 [#]
1	5380	R.D. 4" @ 5288'
		Tape:
	2865	Wabash
	3134	Tapeka
	3476	Ground Lansing
	3689	Lansing
	4265	Marmaton
	4428	Cherokee
	4853	Marrow Shale
	5018	Upper Marrow Sh. Zone
	5072	Lower Marrow Sh. Zone
	5138	Marrow Sh.
Core	5205-56	Rev. 51'
	5342	Base Lower Marrow Sh.
	5351	Miss.
Ref.	5224-34	w/40" - 1000 and
		Sub 4 1/2 boughs & sg
		Plug back to 5100'


State Kansas County Martin
Company P.E.P.L. Co. Well No. 1-21

Farm Behm

Survey

Block No. Sec. 21 Twp. 31^N Range 41^W

Co-Ord. Elev. 3410 RB



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		Ref. 5072-77 w/20 ^N
		1000' and, no shows
		Plug back to 4090
		Ref. 4025-53 w/56 ^N
		Ref. 3994-98 w/8 ^N
		1000' and, no shows
		Plug back to 3260
		Ref. 3248-50 w/80 ^N
		Squeezed - Cleared

Date	Depth	717918
		aft to 3219
		Prof. 3137-45 w/16 ^v
		Prof. 3104-11 w/14 ^v
		Prof. 3086-89 w/6 ^v
		Prof. 3072-77 w/10 ^v
		Prof. 3062-65 w/6 ^v
		Prof. 3055-59 w/9 ^v
		3000 Acid, Subd.
		8 bumph
		Plug back to 3020
		Prof. 2985-95 w/20 ^v
		Prof. 2896-99 w/6 ^v
		Prof. 2878-84 w/12 ^v
		2000 Acid, Gard SH.
		Plug back to 2889
		Subd. 3 bumph, s.s.
		Plug back to 2270
		Prof. 2217-27 w/40 ^v
		1000 acid Subd.
		2 bbl. ndy Suph
		Plug back to 2180
		Prof. 2154-59 w/20 ^v
		1000 Acid no show
		Prof. 2165-75 w/40 ^v
		1000 acid, no show
		Q & A - 11-7-58