

33-16-25W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- MOBLE C. HOOVER  
Farm- Rupp No. 1

SEC. 33 T. 16 R. 25W  
150' NW of C NW NW

Total Depth. 4557'  
Comm. 10-20-62 Comp. 11-3-62  
Shot or Treated.  
Contractor. Hellar Drilling Co., Inc.  
Issued. 3-9-63

County Ness KANSAS



CASING:  
8 5/8" 299' cem w/215 sx.  
4" 4543'

Elevation. 2572' RB

Production. 94 BOPD, NW

Figures Indicate Bottom of Formations.

shale, sand	1317
Blaine	1337
sand-shales	1384
sand-shale & shells	1922
Cimmarron-Anhydrite	1955
shale & shells	2270
shale & lime	2620
lime & shale	2790
lime -(Fort Riley)	3039
Fort Riley	3121
lime-shale	3330
shale & lime	3497
lime & shale	3600
chalk, lime & shale	3747
lime (chalky)	3800
chalk, lime-shale	3901
Kansas City	3909
Kansas City-lime	4000
lime - Kansas City	4053
Kansas City	4131
lime	4195
lime (cherty)	4267
lime	4400
core #1 - Reaming	4430
lime	4495
core #2	4516
core #3	4521
core #4	4526
Mississippi	4550 RTD
Mississippi ?	4557
Total Depth	

TOPS: SCOUT	
Blaine	1317 - 1337
Cimmarron Anhydrite	1922 - 1955
Heebner	3843
Toronto	3866
Lansing	3885
Base Kansas City	4172
Fort Scott	4411
Mississippi Warsaw	4536