

State

Kansas

County

Stafford

Company

Hall Gas & Oil Co.

Well No.

1

Farm

Seever

Survey

Block No.

Sec.

6

Twp.

25⁶

Range

13^w

Co-Ord.


NW SW NE

Elev.

1957 KB

Ry #1

1954 DF



100% - Hall Gas & Oil Co.

200' - 8⁵/₈"

4200' test

NOTE: Show Sketch of Lease and Well Location in Above Space

1650

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

2310

Ft. from E. Line

Date	Depth	
		Spd 6-25-56
6-25-56		MRT
6-26		8 ⁵ / ₈ " @ 185' w/ 225 at cm, 4cc
		4 gal. P.D. 7:15 p.m. 6-25-56
6-27	845-62	Ann.
	1092	Drig.
6-28	1950	Drig. (3 ¹ / ₄ " @ 1891) Having trouble w/ mud pump - "cratered."
6-29		Twisted off drill collars last night. Fished them out.

Date	Depth	717960
		To start submerging pipe today.
	2202	Dreg (Another wash-out on mud pump last night.)
6-30	2632	Dreg.
7-2	3418	Dreg ($3/4^{\circ}$ @ 3360) Losing a little circulation.
7-3	- 3626	Run Ls (-1669)
	- 3647	Losing (-1690)
	3678	On bank for bit trip (1° off)
7-5	Det #1 3689-3734	op 1 hr, cl 15". Rec 150' mdy into. Bhp-1000 ⁺ .
	Det #2 3778-3824	op 1 hr, cl 15". Gas in 23". Rec 125' mdy. gcd, 60' 0 19 cm. 120' clean oil. IF+FF. 120", Bhp-1290 ⁺ .
	3870	Dreg.
7-6	Det #3 3829-70	op 1 hr, cl 15". cl for 18". Rec 30' mud. Pressures - 0.
	Det #4 3879-3902	op 1 hr, cl 15". cl throughout. Gas in 50". Rec 160' 0 19 cm. 50' SW. FP-0 Bhp-620 ⁺ .


State Kansas County Stafford
Company Natural Gas & Oil Co Well No. 1
Farm Seivers

Survey

Block No. Sec. 6 Twp. 25 Range 13 W

Co-Ord. Elev. 1957.5B

no sw ne



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
7-6-56	3936	Reg.
7-7	det #5	3986-4020, up 1 hr. cl 15". Gas in 17". Rec 55' 9 cm. 13HP-1150".
	3992	Miss (-2035)
	4079	Reg.
7-8	-4094	Violet (-2137)
	Det #6	4123-57, up 1 hr cl 15" with cl throughout. Rec 30'

[illegible]