

COMPANY Midwest Gas Co.

SEC. 16 T. 28 R. 17E

FARM Freidline

NO. 4

LOC.

16-28-17E

TOTAL DEPTH

COMM.

SHOT OR TREATED

CONTRACTOR

ISSUED

1223


COMP.

4-29-27

Bakin & Ackerman

COUNTY

WILSON KANSAS



CASING

20

10

15

8

12

6

13

5

23.
422'

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

4 7/8 1116'

line

1223

Total Depth

soil & clay 5
 lime 20
 shale 110
 lime 120
 shale sdy 137
 lime 139
 sand some wtr enough
 to drill with 190

shale 195
 lime 215
 shale 235
 lime 320
 shale blk 325
 lime 330
 shale 355
 lime 340
 shale 355
 lime 380
 shale blk more wtr 385
 lime 432
 shale blk 480
 shale lgt 541
 lime 551
 shale 645
 lime - 40' 682
 shale 720

Steel line run at
 top of 20' 720
 lime-20' 738
 slate blk little gas 746
 lime 751
 slate blk 756

increase in gas
 shale wh 770
 sand 786

increase in gas
 shale wh 835
 lime 838
 shale blue 890
 shale wh 920

shale blue 980
 shale wh 992
 shale blue 1015
 shale sdy 1020
 shale blk 1115
 water sand HFW 1118
 shale blk 1123
 Miss lime 1172
 Mississippi line at
 1123
 sand dk 1177
 showing of gas & oil
 line 1180
 sand brown show oil 1195

Plugged May 20, 1927