

SUTCLIFFE PIPE & SUPPLY

JOE SUTCLIFFE

ORIGINAL

PHONE HE 1-1940 CHANUTE
PHONE TR 8-3601 WICHITA

Well Record

119 S. GRANT, CHANUTE KANSAS
5705 N. BROADWAY, WICHITA, KANSAS

COMPLETE LINE OF NEW & USED PIPE - BELTING - STORAGE TANKS - WIRE LINES

Well No. 7 Farm Uhren Producer Charley Murphy

Location _____ Sec. 16 Twp. 28 Rg. 17E

Elevation _____ State WXXXXX Kans. County Wilson

Kind (Oil, Gas, Water, Dry Hole) _____ Contractor Sutcliffe Pipe & Supply

Producing formation _____ Top _____ Bottom _____

Shot with _____ qts. _____ from _____ to _____

Packer set at _____ Kind _____ Size _____

Liner _____ from _____ to _____ Perforated from _____ to _____

LOG					
Thickness	Strata	Depth	Thickness	Strata	Depth
12	Soil & clay.	12	10	Shale	938
58	Shale	70	5	Good oil sand	943
14	Lime	84		Core #2	
96	Sand & Lime	180	4	Oil Sand	947
65	Lime	245	6	Shale	953
14	Lime	259	1	black oil sand	954
7	Shale dark	266	2	Shale	956
104	Lime w/shale brks.	370		Drilled - (Pocket)	
10	Lime	380	34	Shale	990
110	Shale w/few lime brks.	490			
80	Sand & sandy sh.	580			
11	Shale	591			
39	Lime (40')	630			
33	Shale	663			
17	Lime (20')	680			
10	Shale	690			
5	Lime (5')	695			
2	Slate	697			
12	Sandy shale	709			
11	Sandy shale	720			
10	Shaley sand (Little show of oil)	730			
192	Sandy shale & shale	922			
2	Sand (Show of Core #1 oil)	924			
4	Sandy shale show of oil	928			

Total Depth 990

Open Hole _____

Casing 4 1/2" at 977

Casing 7" at 20

Casing _____ at _____

Cement _____

Tubing _____

Rods _____

Additional Information

Round trip for core barrel. Trip out with core #1. Run 977' of 4 1/2" casing.

Date completed February 11, 1963

O. K.

Superintendent

Started February 6, 1963

737