

State \_\_\_\_\_ County Barber

Company Skelly Well No. 1

Farm M. C. Donovan


Survey \_\_\_\_\_

Block No. \_\_\_\_\_ Sec. 12 Twp. 34 S Range 13 W

Co-Ord. \_\_\_\_\_ Elev. 1565 KB

NW/4

1560 GK



offsets our block  
their #1 Donovan in  
1-34-13

Dr to OCR  
LDC  
AHL 3-20

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
	4664	Miss (-3099)
	dat #1	4668-4710, op 1 hr. cl. 20" Gas in 3" Ga. 572,000. Rec 7' 9cm. 1F-95, FF-80, BHP-1643
		4702-32 Best flow
	dat #2	4700-40, op 155", cl. 20" Gas in 2" Ga. 4,800,000. In 15" ga. 5,750,000. Rec 3' sli 940cm. 1F-665 FF-743, BHP-1665
3-20	4775	R. J. D.

718058

Date

Depth

3-26-56

Perf. 4702-34. Ga. 4,450,000

natural

Traced.

Tested: 41,300,000 cf (KPL)

55,000,000 cf (C.L.G.)

open flow.

4-5-56

Later perf. 4666-90. Traced

w/ 30,000<sup>th</sup> sh, 750<sup>th</sup> S.L.1, 480 Bbls

Kerosene & 85 tubs oil - 6,120,000. <sup>3 3/4" choke</sup>

New potential is app 5 1/4 mil  
greater than first

Test by KPL 45,247,000