


State Kans County Barber
 Company Skelly Well No. 1
 Farm Donovan "C."
 Survey _____
 Block No. _____ Sec. 12 Twp. 34 Range 13
 Co-Ord. _____ Elev. 1625



offsets are Donovan

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
	3886	Heebner
	3973	Douglas
	4083	Lansing (-2458)
	4752	Miss (-3127)
	Set 4736-90, op. 1 1/2 Lr, gd bl.	
	Rec. 120' mud. FP-65-80	
	Bhp - 80 th	
	Set 4790-4840 op. 1 Lr, Gas in 57'	
	Rec. 400' Hr gess. FP-130-	

718061

Date	Depth	
		190, Shp. 1410.
5-18	4890	R.T.D. $5\frac{1}{2}" @ 4890.$
5-25		Cleaned out to 4850.
		Perf 4811-21/60 ^S w/d. 500 MCA
		Cl out. Gas too small to
		measure.
		Traced w/10,000 [#] pl. Gas gas.
		300,000.
		Do plug back + perf 4793-98
		Perf 4793-97. Ga 240,000 nat.
		500 gal MCA. 10,000 [#] 3 ran
		w/240 B Look.
		{ 7L 63 BL inched down + by
		? { Swt 174 BL in 7 hrs. Gase. 150,000.
6-1		Making 2430 + 50,000 cty/d.
		Plan to perf 4801-11
6-8		Perf 4760-74 Swt 15 GORH
		w/50,000 cty.
		750 gal mud acid
		7 B O. 2 B acid w/d. + 7 B FM
		wt. in 20 hrs. May plug.
		abandoned.