

# Hutton Drilling Co.

P.O. Box 158  
Iola, Kansas 66749

33-9-22E

Phone (316) 365-3981  
(316) 365-5916

Graybol-Fatton Company  
Lease: Simpson  
Well # 1,  
Leavenworth County, Kansas  
S.33 T.9 R.22  
API # 15-103-21,000

THICKNESS	FORMATION	TOTAL DEPTH
2	soil	2
20	clay	22
49	sand	71
35	shale	106
5	lime	111
26	shale	137
3	coal	140
84	shale	224
3	lime, brown	227
7	shale	234
15	lime	249
3	coal	252
4	lime	256
22	shale	278
14	lime	292
4	shale	296
4	red bed	300
23	shale	323
29	lime, dark	352
14	shale	366
20	lime	386
8	shale	394
7	lime	401
2	coal	403
2	lime	405
7	shale	412
7	lime	419
16	shale	435
13	lime	448
14	shale	462
9	lime	471
3	shale	474
29	lime	503
7	shale	510
42	lime, (B.K.C.)	552
142	shale	694
6	lime	700
13	shale	713
7	lime	720
40	sand & shale, w/lime str.	760

RECEIVED  
STATE CORPORATION COMMISSION

AUG - 3 1988

CONSERVATION DIVISION  
Wichita, Kansas

(cont'd on page 2 )

33 - 9 - 22E

# Hutton Drilling Co.

P.O. Box 158  
Iola, Kansas 66749

Page 2

Phone (316) 365-3981  
(316) 365-5916

Graybol-Patton Company  
Lease: Simpson  
Well # 1,  
Leavenworth County, Kansas  
S.33 T.9 R.22  
API # 15-103-21,000

THICKNESS	FORMATION	TOTAL DEPTH
5	lime	765
3	shale	768
7	lime	775
3	shale	778
4	lime,w/shale str.	782
76	shale	858
9	sand & shale	867
12	shale	879
10	shale & sand	889
27	shale,sandy	916
86	shale	1002
8	shale & sand	1010
76	shale	1086
4	SAND	1090
70	shale	1160
10	shale,light	1170
66	shale,dark,sandy	1236
66	SAND & shale	1302
21	SAND,"Burgess"(odor & show)	1323
11	shale,light,silty	1334
26	lime,"Mississippi"	1360

T.D. 1360

Set & cemented 108 ft. of 7&5/8 surface....(05-16-88)

Run 1351' of 4½" casing,w/2 cement baskets, 2 centralizers and ball type float shoe....

commenced drilling 05-17-88

completed drilling 05-19-88

RECEIVED  
STATE CORPORATION COMMISSION

AUG - 3 1988

CONSERVATION DIVISION  
Wichita, Kansas