

MAR 07 1977


State Geological Survey
WICHITA, BRANCH

KANSAS DRILLERS LOG

S. 6 T. 16S R. 26 ~~XXX~~ W

Loc. C. SW. SE.

County Ness

640 Acres
N

Locate well correctly

Elev.: Gr. 2648

DF 2651 KB 2653

API No. 15 —————
County Number

Operator

Petroleum, Inc.

Address

67202

800 R.H. Garvey Bldg., 300W. Douglas, Wichita, Ks.

Well No.

Lease Name

1

Basinger

Footage Location

660

feet from (N) ~~XX~~ line

1980

feet from (E) ~~XX~~ line

Principal Contractor

DNB Drilling

Geologist

Toby Elster

Spud Date

10-2-76

Total Depth

4561'

P.B.T.D.

Date Completed

10-29-76

Oil Purchaser

Koch Oil Company

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8"	20#	367'	Common	225	2% gel, 3% c.c.
Production	7-7/8"	5 1/2"	14#	4560'	50/50 Pozmix	100	10% salt W/FRA

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	DP Jets	4541-45'
TUBING RECORD					
Size	Setting depth	Packer set at			
2-3/8" OD RUE	4514'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gal. MSA 10% Acetic Acid	4541-45'
500 gal 15% Nene-E	4541-45'

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
Nov. 18, 1976		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	20	bbls.	-	MCF	8
					bbls.
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
-			24 hr		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Basinger	Oil
S 6 T 16 S R 26 ^{XXX} W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4149-4171 45-60-45-60 Wk Blow, 90' wtry mud, BHP 1122-1068#, IF 17-44, FF 53-80.			Anh. 2070 Hbn. 3891 Lans. 3931 B/KC 4232 Ft.Sc. 4434 Cke. 4458 Miss. 4527 LTD. 4557	(+583) (-1238) (-1278) (-1579) (-1781) (-1805) (-1874) (-1904)
DST #2 4507-40 60-60-60-60 Wk, steady blow. Rec. 195' HO CM IFP 26-62#, ISIP 1140#, FFP 71-107#, FSIP 1068#.				
DST #3 4540-46 60-60-60-60 Wk, stdy blow. Rec. 50' oil, 135' VHO CM. IF 35-53# ISIP 1158#, FFP 62-89#, FSIP 1095#.				
DST #4 4549-61 60-60-60-60 Wk, steady blow. Rec. 50' oil, 100' muddy wtr. IFP 35-53#, FFP 62-80#, ISIP 1175#, FSIP 1131#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	Office Manager
	Title
	Nov 26, 1976
	Date