


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

J. J. HALL
Oswald No. 5-B.

SEC. 11 T. 12 R. 16W
SW NW SE

Total Depth. 3110'
Comm. 7-4-39 Comp. 9-2-39
Shot or Treated. 6500 Gals.
Contractor.
Issued. 9-16-39

County. Ellis



CASING:
15 1/2" 502' P
12 1/2" 684' P
10 " 1029' P (12 jts left in)
8 1/4" 2550' UR 2794' P
7 " 3078'

Elevation.

Production. Pot. 1748 B.

Figures Indicate Bottom of Formations.

cellar	10	lime	1610	lime sft	2610
clay yellow	30	shale	1625	shale	2620
shale dk	75	lime	1640	lime	2624
shale	170	shale red	1650	shale	2626
shale dk LBW 230-40	230	shale	1660	lime	2632
shale sdy	240	lime brkn	1670	shale BW 2635	2645
shale blue	255	shale	1678	lime	2650
shale pink	280	lime shells & shale	1700	shale & lime	2670
red rock	315	shale	1710	shale lime shells	2680
shale blue & red	350	lime	1730	shale gy	2687
sand HFW 350-60	365	red rock	1750	lime	2690
shale	370	lime	1780	shale & shells	2700
red rock & shale	395	shale gy	1785	lime	2705
red rock	415	red rock	1800	shale	2715
sand	435	shale	1805	lime	2720
sand & iron shells	460	lime	1840	sand HFW 2727-2732	2732
sand	497	red rock	1865	lime	2740
shale	502	lime brkn	1890	shale & lime sh	2750
sand	515	shale gy	1905	lime	2755
shale blue	520	shale	1917	shale	2760
sand & iron	530	lime sdy	1940	shale gy	2765
shale blue	540	shale	1960	shale gy & lime shells	2770
sand	550	lime	2010	shale blue	2773
slate	555	red rock	2015	lime	2775
sand	565	lime	2035	lime brkn	2783
slate	585	shale gy	2050	shale lgt	2786
shale blue	595	lime shells & shale	2075	lime brkn	2790
sand	615	shale brown	2090	lime	2800
shale sdy	635	lime	2105	shale (oil sh 1/2 BPH 2802-2805)	2802
sand	660	shale	2115	lime	2811
shale lgt	675	lime	2130	lime brkn (oil sh 2811)	2820
shale	680	red rock	2140	lime	2890
red rock 7BW 695-720	695	lime	2160	lime brkn	2905
sand	720	shale red	2170	lime	2933
red rock	740	shale	2175	shale	2935
shale red	840	lime	2192	lime	2950
red rock 13BW 885-95	960	red rock	2210	shale	2955
shale red	1000	lime	2268	lime	2965
red rock	1022	shale red	2287	lime brkn	2977
lime	1067	lime	2295	lime oil sh 2985-94	2985
sand line corr. SLM 1065-1070		shale	2300	lime sft	3000
red rock	1205	shale & shells	2315	lime	3036
shale blue	1235	lime	2350	shale	3044
red rock	1260	shale & lime	2380	lime	3051
red rock & lime sh	1275	lime	2387	sdv lime Wtr 3051-55	3055
lime	1295	shale	2400	lime	3063
shale	1300	shale & shells	2410	shale red & blue	3068
lime	1325	lime	2420	lime shell	3070
shale blue	1350	shale	2448	shale brown	3075
lime	1395	lime	2456	lime Oswald	3078
lime brkn	1410	shale	2490	lime BW 3086	3089
shale gy	1425	lime 7BW 2500-35	2500	shale	3092
shale & shells	1445	lime sft	2535	lime	3098
shale	1455	lime	2540	shale	3102
lime	1480	shale blue	2548	lime oil 3102-3108	3110
slate	1485	lime	2550	Total Depth.	
shale & lime sh	1520	shale	2568		
lime	1530	lime	2575		
shale	1540	shale BW 2585	2577		
lime	1555	lime brkn	2590		
shale	1570	shale Wtr 2595-2610	2595		