

State

County

Company

Well No.

Farm

Survey

Block No.


Sec.

Twp.

Range

Co-Ord.

Elev.



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date

Depth

3252 KC.

3517 Bo K.C.

3565 Marw

3909 Miss. (-2644)(14' pay)

10 d. 2. #1 - 3923-38 - Op. 1 hr.

925 in 11", ga 44 mcf.

in 15" 44 mcf. 30' (1st) in 45"

Date	Depth	
		718555
		Re. 320' fluid
		85' clear oil
		120' muddy oil
		115' heavy O. B. m.
		BHP - 1530 - 1275 [#]
		Sp. 70 - 130 [#]
	4344	Sp. (-3079)
	D.S. 2. #2	- 4340 - 48 - Op. 1 hr,
		wh. hl. for 10"
		Re. 20 mud
		BHP - 1380 - 1010 [#]
		S.P. - 25 - 30 [#]
	D.S. 2. #3	- 4346 - 53 - Op. 1 1/2 hrs,
		wh. hl. for 1 hr
		Re. 60' oil spotted mud
		BHP - 1675 - 1555 [#]
		S.P. - 30 - 55 [#]
	D.S. 2. #4	- 4351 - 58 - Op. 1 1/2 hrs
		Re. 100' clear mud
		BHP - 1635 - 1570 [#]
		S.P. - 25 - 55 [#]
		(Run clear log)
11-23		5 1/2" C

State

Kansas

County

Sumner

Company

Sunray Mid-Cont. Oil Co.

Well No.

1

Farm

Buech

Survey

Block No.

Sec.

2

Twp.


32^u

Range

3^w

Co-Ord.

Elev.

1265 ^{R/B}

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date

Depth

11-29-60

P.B. to 3961

Perf. 3920-32 1/4 ft.

Swbld. 1 bopd tool.

+ good sho gas

Acidized w/ 500 gal.

11-30 (5:30-7:00 a.m.)

Swbld. 16 bf 1 1/2 oil

+ 1/2 load water in

1 1/2 hrs.) 320# cap.

12-1

Treated w/ 1500 gal. oil

Date	Depth	
		718555
		Swld. 2 1/2 bopph
		plus trace load water.
		To pull try. & swld
		then cag.
12-3		Swld. 3/4 bo & 1/3 bu/ph.
12/4		Swld. 20 bopph. & 8 bu
		To install pumping
		equipment
12-13		Pumped 53 BO - 15 hrs.