

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

22-32-4E

Location. SW SE SW SE  
Lot 9 Blk 2

Sec. 22 T. 32 R 4E.

Casing Record.

County. Cowley

10" 1595 Farm. Fuller  
20" 8 1/2" 2180 Company. G. W. Hinkle.  
15 1/2" 445 65/8" Contr. G. W. Hinkle.  
12 3/4" 1030 53/16" Comm. 3-16-32

No. 1

Comp. 5-23-32



Total Depth. 2665 Shot 100 Quarts Between. 2375-2410  
Correspondence Regarding This Well Should Be Referred To:

Elevation.

Figures Indicate Bottom of Formations.  
Date Issued. 5-28-32

Initial Production.  
Est 250 bbls.,

Formation	Depth	Formation	Depth.
soil	10	lime	1585
lime	40	shale	1595
slate	55	slate white	1630
lime	155	lime	1637
red rock	165	slate blue	1645
lime	170	slate white	1670
slate blue	185	shale cave	1680
lime	190	red rock	1690
red rock	200	shale blue	1695
lime	255	lime	1723
red rock	270	slate white	1760
lime	275	shale	1775
slate	280	slate blue	1810
lime	330	shale	1868
shale	340	lime	1870
lime	350	sdv shale	1875
shale	380	shale	1900
lime	395	lime* HFW 35	1930
red rock	410	sand	1945
slate	425	shale	1975
red rock	442	sdv lime	2055
lime	510	lime hard	2065
shale	530	shale blue	2070
lime	550	slate blue	2075
shale	570	lime hard	2085
lime	575	slate white	2090
shale blue	600	slate blue	2158
lime	625	sand	2175
slate grey	660	lime	2180
slate blue	715	slate	2210
lime	725	shale	2270
slate	735	slate	2364
lime	745	sand	2414
slate dark	840	show of gas. 2400	
shale blue	920	show oil 2410	
slate blue	925	sand	2439
lime hard	945	sdv lime	2485
slate white	950	slate	2560
slate blue	960	lime cave 2655	2665
lime hard	1035	Plugged back to 2416.	
shale	1055	TD.	
slate blue	1075		
lime	1085		
slate blue	1115	10" UR 1812	
lime	1180		
slate blue	1255		
lime white hard	1305		
slate grey	1320		
lime	1355		
red rock	1360		
lime	1435		
lime	1470		
shale blue	1475		
sdv shale	1495		
shale blue	1500		
lime	1510		
sand	1525		
lime	1535		
sand	1550		
lime	1555		
shale	1560		
lime	1570		
shale	1582		