

33-16-25W

D R I L L E R S L O G

#3 Sutton

CASING RECORD:
6 jts. new 8-5/8"
surface casing

COMPANY: Palomino Petroleum
CONTRACTOR: Strata Drilling Company

DESCRIPTION: SE NE NE
Section 33-16S-25W
Ness County, Kansas

TOTAL ROTARY
DEPTH: 4473'

COMMENCED: May 12, 1978
COMPLETED: May 18, 1978

ELEVATION: 2508 G.L.

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock and shale	0	285	Ran 6 jts. new 8-5/8" surface casing, set and cemented @ 272' with 180 sacks common cement, 2% gel, 3% C.C.; cement circulated. Plug down at 11:15 p.m., May 12, 1978.
Shale and sand, shale	285	1864	
Anhydrite	1864	1897	
Shale	1897	2180	
Lime and shale	2180	4035	
Lime	4035	4315	
Lime and Shale	4315	4473	Ran one drill stem test.
			Hole plugged with 50-50 pozmix, 6% gel as follows: 70 sacks @ 640', 20 sacks @ 240', 10 sacks @ 40'. Plug down at 1:45 p.m., May 18, 1978.

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth A. Link