

48525


DEEPENING RECORD

T. M. DEAL OIL & GAS CO.
Dreiling No. 1.

SEC. 4 T. 12 R. 17W
NWc SW

County. Ellis

Total Depth. 3531'
Comm. 5-9-36 Comp. 11-23-36
Shot or Treated.
Contractor.
Issued. 5-15-37



CASING.
15 1/8" 535'
12 3/8" 765'
10 " 1293'
8 1/4" 3016'
6 5/8" 3300'

Elevation.

Production. Pot. 376 B.

Figures Indicate Bottom of Formations.

surface clay	10	shale grey	2070	Show oil	3250-60
shale blue	220	red rock	2095	" "	3280-85
lime	235	lime grey hrd	2205	" "	3300-11
shale blue	345	1 BW 2155		" "	
lime	355	shale blue	2215	lime	3350
slate	365	red rock	2235	Total Depth	
lime	375	lime	2240		
slate	385	red rock	2245		
shale blue	425	lime	2280		
lime grey sft	435	slate blue	2290		
shale blue	440	red rock	2305		
lime	450	lime hrd	2320		
shale	480	red rock	2330		
red rock	490	lime hrd	2340		
shale blue	505	brkn lime	2350		
red rock	515	slate blue	2370		
shale blue	525	lime grey hrd	2385		
red rock	534	red rock	2395		
shale blue	540	lime grey hrd	2410		
lime	560	1 BW 2395			
clay yellow	570	red rock	2449		
red rock	580	lime sdy grey hrd	2500		
shale blue	585	2 BW 2475			
water sand HFW 585	650	slate blue	2510		
slate	660	red rock	2515		
water sand	675	brkn lime	2528		
shale blue	805	lime grey hrd	2618		
water sand HFW 810	875	slate blue	2625		
quick sand	930	brkn lime	2630		
red rock	942	slate blue	2635		
lime hrd	975	lime	2645		
water sand	995	slate blue	2670		
red rock	1013	lime grey hrd	2680		
shale blue	1040	slate blue	2715		
sand	1055	lime grey hrd	2720		
red rock	1070	slate blue	2725		
lime	1075	lime	2730		
red rock	1077	slate blue	2770		
lime	1105	shale grey	2820		
red rock	1275	sdv shale	2835		
chalk	1285	lime	2845		
anhydrite	1320	sdv shale	2850		
red rock	1460	lime	2859		
shale blue	1475	slate	2866		
red rock	1590	lime hrd	2888		
shale blue	1595	shale	2892		
red rock	1625	lime	2898		
shale grey	1680	shale blue	2900		
salt sft	1870	red rock	2905		
shale grey	1945	lime hrd grey	2940		
lime	1960	slate blue	2979		
slate blue	1970	shale	2984		
red rock	1990	brkn lime	3010		
lime grey	2000	lime grey	3038		
slate	2005	slate blue	3042		
lime grey	2015	lime grey	3090		
red rock	2025	sft drk lime	3115		
lime hrd	2040	lime grey	3235		
slate grey	2045	shale blue	3280		
lime grey	2060	lime	3311		

DEEPENING RECORD

T.M.Deal O. G. &
Wolf Creek oil Co.

Comm. 1-5-37
Comp. 3-5-37
Pot. 1297 B.

Old T. D. 3350

lime	3350-3453
slate	3475
wtr sand	3482
lime	3490
shale blue	3495
lime	3502
lime & shale	3506
lime	3518
conglomerate	3522
oil (pay) Siliceous	
lime	3531
Total Depth.	

Siliceous lime 3526-31