


KANSAS CORPORATION COMMISSION

WELL RECORD

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



19-16-26W

API# 15-135-20,569

Lease Name: Horchem "G" Well No. 2 L
 Well Located: NW SW SW Ness Cty
SEC 19 TWP 16S RGE 26W
 Operator: Thunderbird Drilling, Inc.
 Address: P. O. Box 18407, Wichita, Ks.
 Elevation: Ground 2669 D.F. K.B. 2674
 Type Well: (Oil, gas, dry hole) oil

Drilling Commenced: 2-11 1972 Drilling Completed: 2-25 1972
 Well Completed: 19 Total Depth 4554 (4555' well log)
 Initial Production: _____

Casing Record

Size: 8 5/8 Set at 333 Size: _____ Set at _____
 Size: 5 1/2 Set at 4548 Size: _____ Set at _____

Liner Record

Size: _____ Set from _____ To _____

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8 5/8</u>	<u>185</u>	_____
<u>5 1/2</u>	<u>100</u>	_____
Stage Collar @ <u>4374 w/400 sx.</u>		

Perforations

Formation	Perforated Interval and Number Shots
_____	_____
_____	_____
_____	_____
_____	_____

Electric Log Run. (Show type log and depths covered)

Radiation Guard

Contractor: Red Tiger Drilling Co.

Formation Top Bottom

Show Drill Stem Tests,
Well Stimulation and
Production Tests

19-16-26w

Anhydrite	2082
Heebner	3917
Lansing	3959
BKC	4280
Marmaton	4310
Pawnee	4406
Ft. Scott	4456
Cherokee	4481
Miss.	4546

DST #1 4035-65. Opn. 1 1/2 hrs.
Rec. 360' muddy water, FP 69-164, BHP 1099-1038
DST #2 4103-23. Opn. 1 hr. Rec. 20' mud
FP 43-61, BHP 1254-1211
DST #3 4174-4200. Opn 1 hr. Rec. 240' BIP & 30' s
oil and gas cut mud and 180' heavily oil and gas cut
mue and 60' slightly oil and gas cut water.
FP 69-147, BHP 1237-1194.
DST #4 4234-70. Opn. 1 hr. Rec. 65' mud
FP 61-95, BHP 112-95.
DST #5 4320-4410. Opn. 1 hr.
Rec. 70' mud, FP 104-130, BHP 173-156
DST #6 4444-4500. Opn. 1 hr. Rec. 20' mud
FP 61-78, FHP 104-112
DST #7 4524-4554. Opn. 90". Rec. 10' SOCM,
180' HOcm, 60' VHOCM
FP 78-156, BHP 1029-952.



FORMATION	FROM	TO	REMARKS
Shale	0	1190	
Shale & Shells	1190	1490	
Lime	1490	1498	
Shale	1498	1508	
Lime	1508	1520	
Shale & Shells	1520	1545	
Shale-Sand strks	1545	2065	
Red Bed	2065	2084	
Anhydrite	2084	2120	
Red Bed & Shale	2120	2375	
Shale & Shells	2375	2480	
Lime & Shale	2480	2918	
Lime	2918	3021	
Lime & Shale	3021	3120	
Shale & Lime Strks	3120	3231	
Lime & Shale	3231	3960	
Lime	3960	4415	
Lime & Shale	4415	4500	
Lime	4500	4505	
Lime & Shale	4505	4547	
Miss	4547	4555	