


WELL LOG




21-16-26W
SW NW NE

COMPANY Rains & Williamson Oil Co., Inc.
FARM Peters **NO.** 1
RIG. NO. 3
TOTAL DEPTH 4570
COMM. 1-18-72 **COMP.** 1-29-72
CONTRACTOR Rains & Williamson Oil Co., Inc.

SEC. 21 **T.** 16S **R.** 26W
LOG. C SW NW NE

API# 15-135-20,561



CASING
 10 5/8" @ 255' w/ 175 sx.
 12 6"

ELEVATION 2642 KB

13 1 1/2" @ 4560' w/ 150 sx. 60/40 pos, salt sat. **PRODUCTION**
 w/ 3/4 of 1% CFR2, w/ 20 bbl. salt water flush ahead of cement.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	1484
Blaine Anhydrite	1492
Shale	1610
Sand	1800
Shale and Red Bed	2060
Anhydrite	2105
Shale and Lime	3105
Lime and Shale	3845
Lime	4570
Rotary Total Depth	4570

LOG TOPS

ANHY	2066
B ANHY	2105
HEEB	3909
TOR	3927
LANS	3949
BKC	4256
PAWN	4402
FT SC	4461
CHER	4487
CONG	4534
MISS LM	4548
MISS DOL	4554
LTD	4569
RTD	4570

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 11 1972
 CONSERVATION DIVISION
 Wichita, Kansas

