

CHIEF DRILLING CO., Inc.

Drilling Contractors - Oil Producers

SUITE 905 CENTURY PLAZA

WICHITA, KANSAS 67202

22-16-26W

State Geological Survey
WICHITA BRANCH

V. RICHARD HOOVER
PRESIDENT

DAILY DRILLING REPORT

(316) 262-3791

RIG #1

EVEL #1 (#2008)
SE SW NE SEC. 22-16S-26W
NESS COUNTY, KANSAS

ELEVATIONS: 2631 Gr.
2633 D.F.
2636 K.B.

10-04-83 Moving in on location
10-05-83 Finish moving in on location
Spudded in @ 8:30 p.m., Ran 8 jts.
new 8 5/8" 20# casing, 320', set @
323 gr. level, cem w/180 sx., 60-
40 pos mix, 6% c.c., 2% gel, Started
@ 1:30 a.m., completed @ 1:45 a.m.
10-06-83 Waiting on cement
10-07-83 Drilling @ 2092'
10-08-83 Drilling @ 2881'
10-09-83 Drilling @ 3445'
10-10-83 Drilling @ 3939'
10-11-83 Drilling @ 4390'
10-12-83 Running DST #1 4542 - 4580 (Miss.
Dolomite) 30-30-30-30 wk. blow for
15", Rec. 3' mud, IBHP: 34#, FBHP:
34#, IFP: 22#, FFP: 22#
10-13-83 DST #2 4577-4599 (Miss. Dolomite)
4577 - 4599 30-30-60-45 wk. blow for
30", bldg. to fair on the 2nd open
Rec. 130' muddy water, IBHP: 1121#
FBHP: 1121# IFP: 22#, FFP: 57#
T.D. 4599', Plugged w/160 sx. 60-40
pos mix, 2% gel, 3% c.c., 1st plug
@ 2070' w/50 sx., 2nd plug @ 1020'
w/50 sx., 3rd plug @ 330' w/40 sx.,
solid bridge plug @ 40' w/10 sx., 10
sx. in the rathole, started @ 11:30
p.m., completed @ 1:15 p.m. Steve
Durrant state plugger

FORMATION TOPS:

Anhydrite	2052	+	584
Base Anhydr.	2087	+	549
Heebner	3925	-	1289
LKC	3967	-	1331
Stark	4208	-	1572
BKC	4266	-	1630
Marmaton	4315	-	1679
Pawnee	4408	-	1772
Fort Scott	4474	-	1838
Cherokee	4499	-	1863
Miss. Lime	4582	-	1946
Miss. Dolo.	4594	-	1958
RTD	4599	-	1963

RECEIVED
STATE CORPORATION COMMISSION

OCT 18 1984

CONSERVATION DIVISION
Wichita, Kansas