

10-16-26W  
SE-SE-NE

D R I L L E R S    L O G

State Geological Survey  
WICHITA BRANCH

#2 Levi

CASING RECORD: 8 jts. new 20# 8-5/8" surface casing	COMPANY: Beren Corporation	DESCRIPTION: SE SE NE Section 10-16S-26W Ness County, Kansas
TOTAL ROTARY DEPTH: 4535'	CONTRACTOR: Strata Drilling Company	
	COMMENCED: August 13, 1979	
	COMPLETED: August 20, 1979	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock, shale, sand	0	330	Ran 316' new 20# 8-5/8" surface casing; set and cemented @ 321' with 200 sacks 60-40 pozmix, 2% gel, 3% C.C. Cement circulated. Plug down at 8:15 p.m., August 13, 1979.
Shale, sand, shale	330	2050	
Anhydrite	2050	2640	
Lime and shale	2640	2915	
Lime	2915	3115	
Lime and shale	3115	4535	
			Ran 2 drill stem tests.
			Ran 1 electric log.
			Ran 127 jts. new 5 1/2" casing, set at 4526' with 200 sacks 60-40 pozmix, 10% salt. Set DV tool @ 2062' with 300 sacks Halliburton Lite, 100 sacks common. Job completed at 9:00 p.m., August 20, 1979.

STATE OF KANSAS )  
                          ) ss  
COUNTY OF BARTON)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP - 5 1979  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY