

11-16-26W

D R I L L E R S L O G

#1 Ford

CASING RECORD:
365.52' of used 8-5/8"
surface casing.

COMPANY: Okmar Oil Company
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: NE SW SE
Section 11-16S-26W
Ness County, Kansas

TOTAL DEPTH:
4550'

COMMENCED: September 9, 1973
COMPLETED: September 18, 1973

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Clay	0	380	Ran 365.52' of used 8-5/8" surface casing; set and cemented at 370.52' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at 12:45 A. M. September 10, 1973.
Shale w/Sand Streaks	380	940	
Sand	940	1815	
Shale, Lime and Sand	1815	2385	
Lime & Shale	2385	3275	
Lime	3275	3482	
Lime & Shale	3482	3682	
Lime	3682	3925	
Lime & Shale	3925	3990	
Lime	3990	4071	
Lime & Shale	4071	4190	
Lime	4190	4260	
Lime & Shale	4260	4415	
Lime	4415	4550	

Rotary Total Depth: 4550'

D. & A.

Plugged hole as follows: Plugged at 800' with 70 sacks of light cement; plugged at 240' with 20 sacks of light cement; plugged at 40' with 10 sacks of light cement. Plug down at 4:30 A. M. September 18, 1973.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)