

Duplicate

15-125-21548
10-16-26W

D R I L L E R S L O G

Levi #1

CASING RECORD: 7 jts. used 8-5/8" surface casing	COMPANY: Beren Corporation	DESCRIPTION: NW NE NE Section 10-16S-26W Ness County, Kansas
TOTAL ROTARY DEPTH: 4550'	CONTRACTOR: Strata Drilling Company	ELEVATION:
	COMMENCED: December 26, 1978	
	COMPLETED: January 4, 1979	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale, sand	0	315	Ran 7 jts used 8 5/8" surface casing; set and cemented @ 306' with 150 sacks 60-40 pozmix, 50 sacks common cement, 3% C.C.. Cement circulated. Plug down at 12:20 a.m. December 27, 1978.
Shale	315	2050	
Anhydrite	2050	2085	
Shale	2085	2305	
Shale, lime streaks	2305	2930	
Lime, shale	2930	4520	Ran three drill stem tests.
Lime	4520	4550	
			Ran one electric log.
			Ran 113 jts. new 5 1/2" casing. Set at 4535' with 50 sacks Halliburton Lite, 100 sacks common cement. DV tool set at 2038' with 300 sacks Halliburton Lite, 100 sacks common cement. Plug down at 6:00 p.m. January 4, 1979.

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1979
CONSERVATION DIVISION
Wichita, Kansas

Charles W. Steincamp

Charles W. Steincamp

Sworn to and subscribed before me this 4th day of January, 1979.