


CENTRAL PETRO. CO.
Deckert No. 1B.

SEC. 30 T. 12 R. 15W
CNL SE NW

DEEPENING RECORD

Total Depth. 3505'
Comm. 6-16-37 Comp. 7-13-37
Shot or Treated.
Contractor. Harry Gore
Issued. 10-20-50

County. Russell



CASING:
15 1/2" 375'
12 1/2" 620'
10 " 961'
8 1/4" 2490' UR 2707'
6 5/8" 3038'

Elevation.

Production. Pot. 474 B.

Figures Indicate Bottom of Formations.

cellar	10	shale blue	2600	
clay yellow	35	lime	2615	
slate blue	120	slate	2620	
slate grey	135	lime	2637	
shale drk	205	slate	2645	
slate blue	240	lime	2660	
shale sdy	250	slate blue	2665	
slate	295	shale & shells	2680	
red rock	325	shale sdy	2695	
sand wtr	350	shale blue	2705	
red rock	370	lime	2725	
shale blue	375	shale grey	2732	
red rock	395	lime	2758	
shale sdy	400	shale blue	2770	
red rock	415	lime	2985	
sand wtr	425	sh oil 2770		
shale sdy	495	shale	2990	
slate	515	lime	2995	
sand & iron	620	shale	3005	
red rock	950	lime (Dodge)	3022	
lime anhydrite	990	conglomerate	3030	
red rock	1130	shale green	3038	
shale blue	1155	lime (Oswald)	3056	
red rock	1230	shale green	3066	
slate	1320	oil 3040		
salt	1625	lime brown	3076	
slate blue	1635	oil 3036-76		
slate & shells	1715	lime hrd	3090	
red rock	1730	lime brown	3095	
lime	1760	oil 3090-95		
shale	1775	lime hrd	3105	
lime	1810	Total Depth.		
red rock	1825			
lime	1995			
red rock	2005	Dodge Lime Top 3005 Btm 3022		
lime	2040	Oswald Lime Top 3038 Btm 3056	Pay	
red rock	2050	Sh 2770		
lime	2085			
slate	2105	WATER RECORD		
lime	2150	5 BW 240-50		
red rock	2165	HFW 335		
lime	2210	HFW 815		
slate & shells	2225	4 BW 2685		
lime	2235	DEEPENING RECORD		
shale	2250			
lime	2270	Company Schio	Basal sand	3430
slate	2280	Comm. 7-5-46	Granite	5501
lime	2305	Comp. 10-30-46	Total depth	3505
slate	2315	Prod. Pamp. 45 bbls. oil	16 wtr.	
lime	2320	STD 3105		
slate	2325	Osg; 5"-3300; 30 shots	3263-73	
slate & shells	2490	Top sooy sd	3317	
shale blue	2530	Arbuckle	3338	
lime gas 2480	2540		C	
shale grey	2565			